



INVITATION TO E-TENDER
CENTRAL RESERVE POLICE FORCE
O/O THE SPL. DIRECTOR GENERAL, NE ZONE HQR
GUWAHATI (ASSAM) PIN-781023
 Email id: - comdt.engr.nez@gmail.com
 Control Room - **0361 2962524**

.....
Tender Enquiry No.:- **03-NEZ-C/Cell-GC GTY/MW/2026-27**
Dated- 12-07-2026

To,

.....

Dear Sir,

On behalf of the President of India, I invite you to **online bid under two bid system** for the following work to be executed at **Group Centre CRPF Guwahati, Assam-781023.**

Sl. No.	Name of Work
1.	Repairing of Badminton Court at GC CRPF Guwahati, Assam.

2. Details of works are mentioned in **Schedule- "A"** and **"B.O.Q. of Tender"**.
3. If you are in a position to quote for carrying out the proposed works in accordance with the requirements stated in the attached schedule to tender, all documents attached herewith should be properly filled in, signed and submitted through e-procurement site <http://eprocure.gov.in/eprocure/app>. You are further required to furnish along with the aforesaid tender all the information called for, attached list of questionnaire should also be answered and submitted along with documents through e-procurement site <http://eprocure.gov.in/eprocure/cpp>, failing which your tender will liable to be rejected and will not be considered.
4. This tender is not transferable.

Thanking you.

Yours faithfully

Sd/-12-07-2026
LT. COLONEL ANAND KUMAR
COMDT
 Contract Cell, NEZ HQr

[For and on behalf of the President of
India]

SCHEDULE TO TENDER (OPEN TENDER)
CENTRAL RESERVE POLICE FORCE
(Government of India, Ministry of Home Affairs)
O/O THE SPL. DIRECTOR GENERAL, NE ZONE HQR
GUWAHATI (ASSAM) PIN-781023
Email id: - comdt.engr.nez@gmail.com
Control Room - 0361 2962524

Tender Enquiry No.:- 03-NEZ-C/Cell-GC GTY/MW/2026-27 Dated- 12-07-2026

- The intending tenderers must read the terms and condition carefully and submit their tender if they consider themselves eligible and are in possession of all the required documents, through online tender (e-procurement web site in CPP Portal) before due date & time. Tenderers are also advised to go through the Earnest Money, Payment terms and other clauses, terms and conditions of this Tender Enquiry carefully before filling the Tender Application.

TENDER SET IS NOT TRANSFERABLE

e-Tender Enquiry No.	::	03-NEZ-C/Cell-GC GTY/MW/2026-27
Name of work	::	Repairing of Badminton Court at GC CRPF Guwahati, Assam.
Place of work	::	Group Centre CRPF Guwahati, Assam-781023.
Work schedule/Schedule of Quantity	::	Details as per Annexure-I of the Tender enquiry.
Amount of NIT/Estimated Cost	::	Rs. 24,28,936/- only.
E.M.D. (In INR) @ 2% Fixed	::	Rs. 48,579/- only. [Note: - EMD, in favour of DIG Group Centre CRPF Guwahati, Assam-781023 and should be valid at least for 90 days from the date of opening of tender. If thereafter validity of the E.M.D. requires extension, the participated firm will be bound to extend the validity suitably. There is no exemption in EMD and it should be furnished by the bidder mandatorily. If the bidder fails to submit the EMD as specified then his tender will be liable to be rejected summarily]
Procedure for deposit of Earnest Money Deposit	::	Scan copy of EMD is required to be submitted along with tender documents in CPP Portal. Original EMD shall be deposited in the office of the Contract Cell, Central Zone

(EMD)		<u>Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160</u> before the due date of submission of Tender.
Date of Publishing of Tender	::	As per CPP Portal
Start date of submission online/offline documents	::	
Last date of submission online/offline documents	::	
Date of opening of tender	::	
Validity of offer	::	The tender shall remain open for acceptance till 90 days from the date of opening of bid and the accepted rates shall remain valid during the period of execution including the extended period, if any.
Time allowed for completion of work	::	90 days which will be reckoned from the date of issue of work order or the date of handing over of site, whichever is later.

2. Tenders will be opened online on the given date & time at **Contract Cell, Central Zone Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160.**
3. Tenderers are requested to submit their bid/tender documents online through e-procurement in CPP Portal. EMD, Tender Acceptance Letter (On firm's letter head), Integrity Pact (On firm's letter head) documents shall be submitted in original either by hand or by registered/speed post to **Contract Cell, Central Zone Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160.**
4. All Tender documents attached with this invitation to tender including the specifications are sacrosanct for considering any offer as complete offer. It is therefore important that Tender Acceptance Letter which is a written undertaking that all the terms and conditions of the tender are understood and accepted should be signed and submitted along with all documents as required through e-Procurement site http://eprocure.gov.in/eprocure/app_
5. All bidders required to submit earnest money as mentioned above along with their offer. EMD should be paid by the bidder mandatorily. If the bidder fails to submit EMD then his tender will be rejected summarily.
6. All bidders are required to submit their offer in **two bid system.**
7. **The enlistment of the contractor should be valid on the last date of submission of the bid.** In case only the last date of submission of bid is extended, the enlistment of contractor should be valid on the original date of submission of bid.
8. Details required to be furnished by all bidders in the bid (Composite i.e. Technical & Price or financial Bid together) are as under. The bid should contain the following:

(I) Following documents (clear & readable scanned copy of original documents) to be submitted online on CPP Portal.

Caution:	If, Bidder has uploaded irrelevant and blurry documents, these documents will not be considered/accepted and bid will be rejected.
	Contractor who is enlisted with CPWD, MES, BRO, NBCC and Assam PWD will be considered as Enlisted Contractor.
	Contractor who is enlisted with other Government department/PSU etc. will be considered as Non-enlisted contractor.
	In case of Re-tender of above work, Tender Acceptance & Integrity pact submitted by the Bidder remained invalid and fresh documents will be submitted (except EMD) as per NIT.

i.	Tender acceptance letter (In firm's letter head)
ii.	Scanned copy of Earnest Money deposit (As per schedule to tender failing which offers will be summarily rejected).
iii.	Copy of GST registration certificate
iv.	Copy of PAN Card.
v.	Copy of certificate of registration for EPFO and certificate of registration for ESIC (Declaration, if not applicable) failing which offers will be summarily rejected).
vi.	Copy of registration of the firm/contractor for Building Works with CPWD/MES/BRO/NBCC and Assam State PWD in respective categories as per the nature of work and class as per the tender amount or All Documents required for Enlistment as specified in the latest CPWD Enlistment Rules. Note :- (i) <i>Tender limit and validity should be specified clearly or submit relevant documents.</i> (ii) <i>The enlistment of the contractors should be valid on the last date of submission of tenders. In case only the last date of opening of tender is extended, the enlistment of contractor should be valid on the original date of opening of tenders. A copy of Registration Certificate as a "Contractor" issued by competent authority of CPWD/MES/BRO/NBCC and Assam State PWD is mandatory to be uploaded with the tender documents by the Bidder(s). In case validity of enlistment/registration/trade license expired and the concerned firm has applied for renewal to the concerned department or ministry, the relevant documents of such renewal application along with undertaking of the firm should be essentially submitted with their bid.]</i>
vii.	Contractors/Bidder (Enlisted and Non-enlisted) will have to submit past performance for satisfactorily completed similar works of CPWD//BRO/MES/NBCC and Assam State PWD as a prime contractor during last 05 (five) years equal to following value: - a. One similar completed work costing not less than the amount equal to 80% of the estimated cost put to tender Or b. Two similar completed works each costing not less than the amount equal to 60% of the estimated cost put to tender Or c. Three similar completed works each costing not less than the amount equal to 40% of the estimated cost put to tender Note :- Bidder has to submit on-line scanned copy of work order along with its work

	completion certificate of similar nature work equal to required value during last five years (not before 01/04/2021) issued by not below the rank of Executive Engineer or equivalent. - The completion certificate should include the name of work, agreement no., estimated cost, tendered/awarded cost, stipulated date of start, completion cost and actual date of completion of work etc. Similar works means Construction/Repairing/Renovation/upgradation of building works
viii.	Check list as per Appendix-‘B’ after compliance.
ix.	Information regarding any litigation or arbitration resulting from contracts executed by the bidder in the last five years or currently under execution as provided. Bidder has to submit on-line scanned copy of an information regarding litigation, arbitration, black listing, debarring etc. This document must be uploaded on line duly signed by the bidder.
x.	Bidder has to submit on-line scanned copy of an affidavit duly signed stating that the near relations defined as first blood relations, and their spouses is/are not working in CRPF. If working, give details for the same. (a relation shall mean wife, husband, parents, grandparents, children, grandchildren, brothers, sisters, uncles, aunts, cousins and their corresponding in-laws) Note:- Affidavit should not be old more than 06 months from bid submission end date.
xi.	Bidder has to submit on-line scanned copy of an affidavit duly signed stating that no retired personnel in his employment is working who retired within last two years from CRPF. If employed, give details for the same. Note:- Affidavit should not be old more than 06 months from bid submission end date.
xii.	Partnership Agreement of the firm if the firm is a partnership firm. (If no papers submitted with the bid it will be assumed that the firm is a Single/Sole Proprietary and will be fully responsible if found false at later stage)
xiii.	Non-enlisted bidders are required to submit i. Banker's Certificate of Rs. 08 lakhs (Proforma as Appendix-C) OR Net worth Certificate of Rs. 04 lakhs (proforma as Appendix-D) AND (ii). Average Annual Turnover Certificate of Rs. 08 lakhs (Proforma as Appendix-E) on works during the last three financial years from a Chartered Accountant. Note:- Documents should not be old more than 06 months from bid submission end date.
xiv.	All pages of the tender documents duly completed & signed in all respect by the authorized signatory of the firm/contractor under the seal.

(I I) . Documents to be submitted in original manually or by **registered/speed post/Courier t o Contract Cell, Central Zone Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160.**

1.	Tender acceptance letter (On firm's letter head)
2.	Earnest Money deposit (in original)
3.	Integrity Pact (on firm's letter head)

9. Following should be noted and kept in mind while submission of rate in price bid format of C.P.P Portal-
- Price should only be quoted as per price bid format/B.O.Q along with tender documents at e- procurement site http://eprocure.gov.in/eprocure/app_
 - The price bid in B.O.Q format / template should not be modified and replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for the tender. Bidders are allowed to enter the Bidder Name and Values only.
10. Bidder should deposit earnest money with required validity along with their Tender. Earnest Money should be in form of **Account payee Demand Draft, Fixed Deposit Receipt, Banker's Cheque** from any of the commercial banks in an acceptable form in favour of **DIG Group Centre CRPF Guwahati, Assam-781023.**
11. The tender documents are consisting of specification, schedule of quantities of works to be provided and terms and conditions of this contract to be complied with other necessary documents.

Signature of the bidder

Sd/- 12-07-2026
LT. COLONEL ANAND
KUMAR
COMDT

Contract Cell, NEZ HQr
[For and on behalf of the President of
India]

Appendix-'A'

TENDER ACCEPTANCE LETTER **(To be given on Firm's/Company's Letter Head)**

Date :-

To

Subject :- Acceptance of Terms & Conditions of Tender.

Tender Reference No :- _____

Name of Tender/Work : _____

Dear Sir,

1. I/We have downloaded/obtained the tender document(s) for the above mentioned 'Tender/Work' from the web site(s) namely..... as per your advertisement, given in the above-mentioned website(s).
2. I/We hereby certify that I / we have read the entire terms and conditions of the tender documents from Page No. _____ to _____ (including all documents like annexure(s), schedule(s), etc.) which form part of the contract agreement and I / we shall abide hereby by the terms / conditions / clauses contained therein.
3. The corrigendum(s) issued from time to time by your department/ organizations too have also been taken into consideration, while submitting this acceptance letter.
4. I/We hereby unconditionally accept the tender conditions of above-mentioned tender document(s) / corrigendum(s) in its totality/entirety.
5. In case any provisions of this tender are found violated, then your department/ organization shall without prejudice to any other right or remedy be at liberty to reject this tender/bid including the forfeiture of the full said earnest money deposit absolutely.

Yours Faithfully,

(Signature of the Bidder, with Official Seal)

SIGNATURE OF BIDDER

Appendix-"B"

Check list for Bidder

(Tenderers should check following requirements for compliance before submission of the tender documents)

Sl. No.	Requirements to be checked by the tenderer before submission of the tender	Compliance (To be indicated with "YES" after Compliance of the requirements)
1.	Whether Tenderers has submitted required Earnest Money Deposit with their bid as specified? (As per schedule to tender failing which offers will be summarily rejected).	
2.	Whether rates have been quoted only as per price bid format / B.O.Q along with tender documents?	
3.	Whether rates have been quoted inclusive of all taxes including GST (ESI and EPF contributions on the part of employer in respect of this contract shall be paid by the contractor. The EPF & ESIC contributions on the part of the employer paid by the contractor shall be reimbursed by the department to the contractor on actual basis with site of work at "DIG Group	

	Centre CRPF Guwahati, Assam-781023" only on producing original receipt of EPF & ESIC paid by the contractor to Govt. organization. (It may also be noted that the quoted rates are inclusive of all taxes.)	
4.	Whether copy of GST & PAN Card submitted?	
5.	Whether copy of registration of the firm/contractor with CPWD, MES, BRO, NBCC & Assam PWD submitted?	
6.	Whether copy of registration of certificate registration of EPFO and certificate of registration of ESIC submitted? (Declaration, if not applicable) (Failing to submit the certificates offers will be summarily rejected).	
7.	Satisfactorily completed as a prime contractor at least one similar work of 80% value or two works of at least 60% value or three works of at least 40% value. Bidder has to submit on-line scanned copy of certificate of Work Order along with Work Completion certificate of similar nature work of CPWD/NBCC/BRO/MES and Assam State PWD equal to required value during last Five years issued by not below the rank of Executive Engineer. #Similar works means -construction/Repairing of Building works along with allied services.	
8.	Non-enlisted bidders are required to submit i. Banker's Certificate of Rs. 08 lakhs (Proforma as Appendix-C) OR Net worth Certificate of Rs. 04 lakhs (proforma as Appendix-D) AND (ii). Average Annual Turnover Certificate of Rs. 08 lakhs (Proforma as Appendix-E) on works during the last three financial years from a Chartered Accountant. Note:- Documents should not be old more than 06 months from bid submission end date.	
9.	Tenderers should mention that Business dealing with their firms has not been banned by any Govt. / private agencies.	
10.	Tenderer should ensure to sign each page of the Tender documents with name, designation of the authorized signatory under his seal.	
11.	If the tenderer wants to mention any specific condition, it should be mentioned on the covering/forwarding letter in letter head only which will be placed on the first page of the bid. Such condition mentioned in any other document shall not be given any consideration.	
12.	Tenderers should mention their address for communication with Telephone/Fax Number and e- mail address.	
13.	Whether all the Points under heading "Terms & Conditions", "Additional Conditions" and instructions are fully abided by the contractor or not?	
14.	Whether all the requisite documents as asked in tender Schedule of inviting tender notice have been submitted by the tenderer?	
15.	Whether the firm has enclosed valid documents if the firm is a partnership proprietary in nature? (If no papers submitted with the bid it will be assumed that the firm is Single/Sole Proprietary)	
16.	Whether any other relevant documents which the firms wish to submit as a part of offer?	
17.	Tender acceptance letter (In firm's letter head)	
18.	Integrity Pact (on firm's letter head)	

SIGNATURE OF THE BIDDER

Appendix-“C”**FORM OF BANKER'S CERTIFICATE FROM A COMMERCIAL BANK**

This is to certify that to the best of our knowledge and information Shri/Smt/M/s.....having registered address, a customer of our bank, is/are respectable and can be treated as reliable for any engagement up to a limit of Rs..... (Rupees)

This certificate is issued without any guarantee or responsibility on the Bank or any of the officers. This certificate is issued on the request of Shri/Smt/M/S..... for obtaining Works tender in CRPF namely..... (Name of Works).

(Signature) For the Bank

Note:

1. **Banker's certificates should be on the letter head of the bank, addressed to enlisting authority.**
2. **In case of partnership firm, the certificate shall include names of all partners as recorded with the bank.**

Appendix-“D”**FORM OF CERTIFICATE OF NET WORTH FROM CHARTERED ACCOUNTANT**

It is to certify that as per the audited balance sheet and profit & loss account during the financial year... .., the Net worth of Shri/Smt/M/s..... (Name & Registered Address of individual/firm/company), is Rs..... after considering all liabilities. It is further certified that the Net worth of the individual/firm/company has not eroded by more than 50% during the last three years ending on 31st March Unique Document Identification Number (UDIN).....

(Signature of Chartered Accountant)

(Name of Chartered Accountant) :
Membership No. of
ICAI :
Date and seal :

Appendix-“E”**FORM OF CERTIFICATE OF ANNUAL TURNOVER ON WORKS FROM CHARTERED ACCOUNTANT**

Certified that following is the annual turnover on works of the individual/firm/company as per returns filed with Income Tax Department for the past 3(three) financial years.

Name and registered address of individual / firm /company :
.....

S. No.	Financial Year	Annual Turnover on Works in Rs. lakhs

Unique Document Identification Number (UDIN).....

(Signature of Chartered Accountant)
(Name of Chartered Accountant) :
Membership No. of ICAI :
Date and seal

Appendix-"F"

UNDERTAKING

It is stated that my firm is not involved in any kind of litigation or arbitration from contracts executed by firm and also not blacklisted or debarred by any department of central/state Government & PSU in last five years from bid submission end date.

Place :-

Date :-

Signature of bidder
(with seal of firm/bidder)

Appendix-"G"

(To be executed on a non-judicial stamp paper of appropriate value as per state laws and notarized)

AFFIDAVIT

I , [Full Name of Proprietor], son/daughter/wife of [Father's/Husband's Name], aged about [Age] years, residing at [Full Residential Address], do hereby solemnly affirm and declare as follows:

1. I am the sole owner and proprietor of the firm running under the name and style of M/S [Name of the Proprietorship Firm], having its principal place of business at [Full Business Address].
2. As the sole proprietor of the said firm, I am fully authorized, competent, and legally entitled to sign, submit, execute, and represent the firm in all matters, documents, and contracts relating to Tenders issued by the DIG Group Centre CRPF Guwahati, Assam-781023.
3. The financial liabilities, assets, and business transactions of the said firm are entirely my personal responsibility as the sole owner.
4. All documents, certificates, and credentials submitted by me

or my authorized representative for this tender are true, genuine, and valid.

5. The contents of this affidavit are true and correct to the best of my knowledge and belief. No part of it is false, and nothing material has been concealed therefrom.

DEPONENT

(Signature of the Proprietor)

Name: _____

Designation: Sole Proprietor

Firm Name: M/s _____

Date: _____

Place: _____

NOTICE INVITING TENDER

The **Commandant Engineer, NE Zone Hqr CRPF, Guwahati, Assam** invites online item rate bids for & on behalf of the President of India from approved and eligible qualified contractors of **CPWD, MES, BRO, NBCC and Assam PWD** for **"Repairing of Badminton Court at GC CRPF Guwahati, Assam"**. The estimated cost put to the work is **Rs. 24,28,936/- (Rupees twenty four lakh twenty eight thousand nine hundred thirty six)** only including all taxes.

1. The enlistment of the contractors should be valid on the last date of submission of bids. In case the last date of submission of tender is extended, the enlistment of contractor should be valid on the original date of submission of bids.
2. Agreement shall be drawn with the successful bidders on prescribed form of CPWD (or other Standard Form as mentioned) which is available as a Govt. of India Publication and also available on website www.cpwd.gov.in. Bidders shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.
3. The work has to be completed by within **90 days** from the date of issuing of work order or from the first date of handing over of the site, whichever is later, in accordance with the phasing, if any, indicated in the bid documents. Site of work is within the RESTRICTED AREA.
4. The site for the work is available.
5. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents except Standard General Conditions of Contract Form can be seen from CPP Portal (<http://eprocure.gov.in/eprocure/app>).

6. After submission of the bid the contractor can re-submit revised bid any number of times but before last time and date of submission of bid as notified.
7. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of bid as notified.
8. Bidder should deposit earnest money with required validity along with their Tender, Earnest Money should be in form of Account payee Demand Draft, Fixed Deposit Receipt, Banker's Cheque from any of the commercial banks in an acceptable form in favor of "**DIG Group Centre CRPF Guwahati, Assam-781023.**"

The Earnest Money shall be scanned and uploaded to the e-Tendering website within the period of bid submission. The physical EMD of the scanned copy of EMD uploaded shall be deposited in original at **Contract Cell, Central Zone Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160** failing which the tender shall be rejected.

Interested contractor who wish to participate in the bid has to make following payments in the form of Demand Draft / Pay order or Banker's Cheque of any Scheduled Bank to the e-Tendering website within the period of bid submission:

- i. Copy of Enlistment Order and other documents as specified in the press notice shall be scanned and uploaded to the e-Tendering website within the period of bid submission. Original Demand Draft of Earnest Money Deposit (EMD) shall be deposited in the office of the **Contract Cell, Central Zone Hqr, CRPF, Street No. 299, DJ Block, New Town Area-III, Near Jalvayu Tower, New Town, Kolkata (W.B) Pin-700160** before the due date of submission receipt of tender bids
 - ii. The bid/tender submitted shall be opened as per timing specified on CPP Portal.
1. The bid/tender submitted shall become invalid and cost of bid shall not be refunded if:-
 - i. The bidders are found ineligible.
 - ii. The bidders do not upload all the documents (including Labour Licence, GST registration, EPFO & ESIC registration, PAN card and copy of registration/enlistment) as stipulated in the bid document including the undertaking about deposition of physical EMD of the scanned copy of EMD uploaded.
 - iii. Any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically in the office of tender opening authority.
 2. The contractor whose tender is accepted will be required to deposit **PERFORMANCE SECURITY for an amount of Five percent (5%) of the value of the contract within a period of 07 (SEVEN) days after the Tender is accepted by the Competent Engineering Authority. Performance Security may be furnished in the form of an Fixed Deposit Receipt from a commercial bank in an acceptable form.** Performance Security should remain valid for a period of 180 days (06 months) beyond the date of completion of all contractual obligation of the

supplier including warranty obligations if any. In case the contractor fails to deposit the performance security within the stipulated period including extended period, if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor.

3. The contractor whose bid is accepted will also be required to furnish either copy of applicable licenses/registrations or Proof of applying for obtaining labour licenses and registration with EPFO & ESIC within the period specified in **Schedule-“F”**. Failing to submit the above certificates / documents, offers will be summarily rejected. The reimbursement of EPF & ESI contributions paid by the contractor on the part of employer is to be made on submission of documentary proof of payment provided the same is in order.
4. Intending Bidders may inspect and examine the site and its surroundings and satisfy themselves before submitting their bids as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. A bidder shall be deemed to have full knowledge of the site and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The bidders shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by a bidders implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.
5. The Competent Engineering Authority on behalf of the President of India does not bind itself to accept the lowest or any other bid and reserves to itself the authority to reject any or all the bids received without the assignment of any reason. All bids in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the bidders shall be summarily rejected.
 - Canvassing whether directly or indirectly, in connection with bidders is strictly prohibited and the bids submitted by the contractors who resort to canvassing will be liable for rejection.
14. The competent authority on behalf of President of India reserves to himself the right of accepting the whole or any part of the bid and the bidders shall be bound to perform the same at the rate quoted.
15. No Engineer of Gazetted Rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the prior permission of the Government of India in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before submission of the bid or before submission of the bid or engagement in the contractor's service.
16. The bid for the works shall remain open for acceptance for a period of Ninety

(90) days from the end date of submission of bids, if any bidders withdraws his bid before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the bid which are not acceptable to the department, then the Government shall, without prejudice to any other right or remedy, be at liberty to forfeit 100% of the said earnest money as aforesaid. Further the bidders shall not be allowed to participate in the re-bidding process of the work.

17. This notice inviting Bid shall form a part of the contract document. The successful bidders/contractor, on acceptance of his bid by the Accepting Authority shall within 15 days from the stipulated date of start of the work, sign the contract consisting of:-
 - a. The Notice Inviting Bid, all the documents including additional conditions, specifications and drawings, if any, forming part of the bid as uploaded at the time of invitation of bid and the rates quoted online at the time of submission of bid and acceptance thereof together with any correspondence leading thereto.
 - b. Standard C.P.W.D. Form 7/8 or other Standard C.P.W.D. Form as applicable.

Sd/- 12-07-2026

LT. COLONEL ANAND KUMAR
COMDT

Contract Cell, NEZ HQr

[For and on behalf of the President of India]

GOVERNMENT OF INDIA
CENTRAL RESERVE POLICE FORCE

STATE: **Assam**
Guwahati

Work Site : **Group Centre CRPF**

ITEM RATE TENDER & CONTRACT FOR WORKS

Tender **Repairing of Badminton Court at GC CRPF Guwahati, Assam.**
for the
work of

- I. To be submitted online through website
<http://eprocure.gov.in/eprocure/app>
- II. To be opened in online at **Contract Cell, Central Zone Hqr, CRPF,
Street No. 299, DJ Block, New Town Area-III, Near Jalvayu
Tower, New Town, Kolkata (W.B) Pin-700160.**

T E N D E R

I/We have read and examined the Notice Inviting Tender, Schedule A, B, C, D, E & F, Specifications applicable, Drawings & Designs, General Rules and Directions, Conditions of Contract, Clauses of Contract, Special Conditions, Schedule of Rate and other documents and Rules referred to in the conditions of contract and all other contents in the tender document for the work.

I/We hereby tender for the execution of the work specified for the President of India within the time specified in Schedule-"F", viz. Schedule of Quantities and in accordance in all respects with the Specifications, Designs, Drawings and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause-11 of the Conditions of Contract and with such materials as are provided for, by and in respects in accordance with, such conditions so far as applicable.

We agree to keep the tender open for Ninety (90) days from the date of opening of tender and not to make any modifications in its terms and conditions.

A sum of **Rs. 48,579/- (Rupees, forty eight thousand five hundred seventy nine)** only is hereby forwarded in Bank Draft/ FDR of a Scheduled Bank/ Demand Draft of a scheduled bank as earnest money. If I/We, fail to furnish the prescribed performance guarantee within prescribed period, I/We agree that the said President of India or his successors, in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/We fail to commence work as specified, I/ We agree that President of India or the successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said performance guarantee absolutely. The said Performance Guarantee shall be a guarantee to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the tender form.

Further, I/We agree that in case of forfeiture of Earnest Money or Performance Guarantee as aforesaid, I/We shall be debarred for participation in the re-tendering process of the work. I/We undertake and confirm that eligible similar work(s) has/have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/We shall be debarred for tendering in CRPF in future forever. Also, if such a violation comes to the notice of Department before date of start of work, the Engineer-in-Charge shall be free to forfeit the entire amount of Earnest Money Deposit/Performance Guarantee

I/We hereby declare that I/We shall treat the tender documents, drawings and other records connected with the work as secret/confidential documents and shall not communicate information/derived there from to any person other than a person to whom I/We am/are authorized to communicate the same or use the information in any manner prejudicial to the safety & integrity of the State.

Dated :

Signature of Contractor

Witness:

Postal Address

Address:

Occupation:

SCHEDULES (A TO F)

SCHEDULE - "A"

Name of work :- **Repairing of Badminton Court at GC CRPF Guwahati, Assam.**

Schedule of quantities: - As per BOQ:-

SCHEDULE - "B"

Schedule of materials to be issued to the contractor.

S.No.	Description of item.	Quantity. words of at which the material will issue be charged to the contractor	Rate in figures & Place
(1)	(2)	(3) (4)	(5)

----- **NIL** -----

SCHEDULE - "C"

Tools and plants to be hired to the contractor

SL. No.	DESCRIPTION.	HIRE CHARGES PER DAY	PLACE OF ISSUE
----------------	---------------------	-----------------------------	-----------------------

----- **NIL** -----

NOTE :-ALL THE TOOLS, PLANTS AND MACHINERY REQUIRED FOR CARRYING OUT THE SUBJECT WORK SHOULD BE OWNED/REGISTERED/LEASED EITHER IN THE NAME OF THE SOLE PROPRIETOR OF THE FIRM OR THE NAME OF FIRM AND THE CONTRACTOR SHALL ALSO

MEET THE MINIMUM REQUIREMENT OF TOOLS, PLANTS AND MACHINERY SUCH AS VIBRATORY ROLLERS, PNEUMATIC WHEELED ROLLER, FULLY AUTOMATIC CONCRETE BATCHING PLANT, CONCRETE PAVER FINISHER ,CONTINUES TYPE HOT MIX PLANT, PAVER FINISHER (HYDRAULICALLY CONTROLLED SENSORS OPERATED ELECTRICALLY FOR THE PAVE FINISHER (HYDRAULICALLY CONTROLLED), BULL DOZERS, ROAD ROLLERS, DRILLING MACHINES, CONCRETE MOBILE WEIGH BATCHERS, TRANSIT MIXERS ONE BAG CAPACITY CONCRETE MIXER(DIESEL), VIBRATORS (NEEDLE AND PLATE TYPE), TRUCKS/ TIPPERS, TOTAL STATIONS, CONCRETE CUBE TESTING MACHINE(HYDRAULICALLY OPERATED), FULLY AUTOMATIC CONCRETE BATCHING PLANT AND ANY OTHER TOOLS, PLANTS AND MACHINERY REQUIRED FOR THE WORK AS PER GOOD ENGINEERING PRACTICE/RELEVANT IS-CODES WHICHEVER APPLICABLE.

SCHEDULE - "D"

Extra schedule for specific requirements/ documents for the work, if any - NIL

SCHEDULE- "E"

Reference to General Conditions of Contract: - General Conditions of Contract for CPWD Works 2023 with upto-date amendments.

Name of Work	Repairing of Badminton Court at GC CRPF Guwahati, Assam.
Estimated Cost of work	Rs.24,28,936/- (Rupees twenty four lakh twenty eight thousand nine hundred thirty six) only.
Earnest Money	Rs. 48,579 /- (The EMD will be returned post receipt of Performance Guarantee)
Performance Guarantee	5% of tendered value (It shall be valid up to the stipulated date of completion Plus 180 days beyond that)
Security Deposit	2.5 %

SCHEDULE- "F"

General Rules & Directions : -

Officer Inviting Tender : Commandant (Engr)

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with Clauses 12.2 & 12.3

See below

Definitions: -

- Engineer-In-Charge **AC Engr** or Designated by Comdt (Engr)
- Accepting Authority Comdt (Engr),
- Percentage on cost of Materials and labor to Cover all overheads and Profits 15%
- Standard Schedule of Rates DSR
- Department CRPF

Standard CPWD contract Form CPWD form 8 & General Conditions of Contract for CPWD Works-2023 with up to date correction slips

Clause-1

- i. Time allowed for submission of Performance guarantee Programme Chart (Time & Progress) and from the date of issue of letter of acceptance
- ii. Maximum allowable extension beyond the period as provided in (i) above

07 Days

10 days by CEA

Clause-1A-

Recovery of Security Deposit of GCC

Applicable

C
l
a
u
s
e
-
2
:
-

Authority for fixing compensation under clause 2.

Comdt (Engr)

Clause-2A

Whether Clause 2A shall be applicable

No

Clause- 3 :-

Applicable

Clause 3A:-

Applicable

Clause 4 :-

Applicable

Clause-5:-

Applicable

Time allowed for execution of work

90 Days

Authority to decide

- I.

Extension of time	Comdt (Engr)
II. Rescheduling of mile stones	Comdt (Engr)
III. Shifting of date of start in case of delay in handing over of site	Comdt (Engr)
Clause-6	
Computerized Measurement Book	No, Duly Signed printed copy
Clause-7A	
Whether Clause 7A shall be applicable	Applicable
Clause 8	
Completion Certificate and Completion Plans	Applicable
Clause-8A	
Completion Plans to be Submitted by the Contractor	Applicable.
Clause-9	
Payment of Final Bill	Applicable.
Clause 9A	
Payment of Contractor's Bills to Banks	Applicable.
Clause-10A	
Materials to be provided by the Contractor	Applicable
Clause-10-B	
i. Secured Advance on Materials	No
ii. Whether Mobilization advance will be paid	No
Clause-10C:-	

Payment on Account of Increase in Prices/ Wages due to Statutory Order(s)

Not applicable

Clause-10 CA

Payment due to variation in prices of materials after receipt of tender

Not applicable

Clause-10-CC:-

Payment due to Increase / Decrease in Prices/ Wages (excluding materials covered under clause 10 CA) after Receipt of Tender for Works

Not applicable

Clause 10 D

Dismantling of a structure The contractor shall treat all materials obtained during dismantling of a structure at the site for a work, etc. as Government's property and such materials shall be the best advantage of Government according to the instructions in writing issued by the Engineer-in-Charge.

Clause -11

Execution of the work The contractor shall execute the whole and every part of the work in the most suitable manner both as regards materials and otherwise in every respect in strict accordance with the specifications. The contractor shall also conform exactly, fully and faithfully to the design and instructions in writing in respect of the work signed by the Engineer-in-Charge and the Architect. The contractor shall furnish free of charge one copy of the contract documents together with specific instructions and drawings as are not included in the standard specifications of Central Public Works Department, Government of India, or in any Bureau of Indian Standard or any other, published by the Government, or in any other printed publication referred to elsewhere in the contract. The contractor shall comply with the provisions of the contract and with the care and diligence required in the works and provide all labour and materials, tools and plants including for measurement of all works, structural plans and other things of temporary or permanent nature for the execution and maintenance in so far as the necessity for providing these, is specified or inferred from the contract. The Contractor shall take full responsibility for adequacy of all the works and methods of construction.

Clause 12

Authority to decide Deviation

Comdt. (Engr)

Comdt (Engr)

Comdt (Engr)

Contractor If the contractor or his working people or servants shall break, deface, injure or damage any building in which they may be working, or any building, road, road kerb, fence, enclosure, drains, electric or telephone post or wires, trees, grass or grassland, or cultivated land or the premises on which the work or any part is being executed, or if any damage shall be done while in progress, from any cause whatever or if any defect, shrinkage or other defect occurs in the work within **twelve months (six months in the case of work costing Rs. Ten lacs or more)** after a certificate final or otherwise of its completion shall have been issued, the Contractor shall upon receipt of a notice in writing on that behalf make the same good at his own cost. The Engineer-in-Charge shall cause the same to be made good by other workmen and the cost shall be recovered from any sums that may be due or at any time thereafter may become due to the Contractor from the Government or his security deposit or the proceeds of sale thereof or of a sufficient portion thereof. The Contractor's security deposit of the contractor shall not be refunded before the expiry of twelve months after the issue of the certificate final or otherwise, of completion of work. Provided that in the case of road works or other civil works, the Engineer-in-Charge, half of the security deposit is sufficient, to meet all liabilities under this contract, half of the security deposit will be refundable after six months and in the case of other works, half after twelve months of the issue of the said certificate of completion. In case of maintenance or operation works of E&M services, the security deposit deducted from contractors shall be refundable after Two months from the date of final payment or within Two months from the date of completion of the maintenance contract whichever is earlier.

Tools & Plant etc. The contractor shall provide at his own cost all materials machinery, tools & plant etc. In addition to this, appliances, implements, other plants, ladders, cordage, temporary works required for the proper execution of the work, whether original, and whether included in the specifications or other documents forming part of the contract, to in these conditions or not, or in- Charge as to any matter as to which under the

itled to be satisfied, or which he is entitled to require together with carriage ther work. The contractor shall also supply without charge the requisite number of per nd materials, examination at any time and from time to time of the work or mater g, the same may be provided by the Engineer-in-Charge at the expense of the cor ses may be deducted, from any money due to the contractor, under this contract om his security deposit or the proceeds of sale thereof, or of a sufficient portion tl

Clause- 19

Labour L
aws to b
e compli
ed by the
contracto
r

Applicable

Clause -19A

No labo
ur belo
w the a
ge of Ei
ghteen
years s
hall be
employ
ed on t
he work

Applicable

Clause -19C

Applicable

Clause -19D

Applicable

Clause -
19K

Emplo yment of skill ed/ se mi-skill ed wor kers

The contractor shall, at all stages of work, deploy skilled/semi-skilled tradesmen possess certificate in particular trade from CPWD Training Institute/Industrial Train Institute of construction Management and Research (NICMAR)/ National Academ C or any similar reputed and recognized Institute managed/ certified by State/Cel number of such qualified tradesmen. The contractor shall submit number of man ect of each trade, its scheduling and the list of qualified tradesmen along with re recognized Institute to Engineer in charge for approval. Notwithstanding such app n are found to have inadequate skill to execute the work of respective trade, the ute such tradesmen within two days of written notice from Engineer in- Charge. F ontractor to obtain approval of Engineer-in-Charge or failure to deploy qualified tr compensation to be paid by contractor at the rate specified in schedule 'F' per su Decision of Engineer in Charge as to whether particular tradesman possesses rec t of compensation in case of default shall be final and binding. Provided always, t

his clause, shall not be applicable for works with estimated cost put to tender be less than Rs. 10 Crores. For work costing more than Rs. 10 Crores, and up to Rs. 50 Crores, the contractor shall provide training as per National Skill Development Corporation (NSDC) norms for at least 30% of the unskilled workers engaged in the project in co-ordination with the CPWD Regional Training Institute & National Skill Development Corporation (NSDC) for certification at the level of skilled/semi-skilled workers. For works costing more than Rs. 50 Crores, the contractor shall arrange on site training as per National Skill Development Corporation (NSDC) norms for at least 30% of the unskilled workers in co-ordination with the CPWD Regional Training Institute & National Skill Development Corporation (NSDC) for certification at the level of skilled/semi-skilled tradesmen. The cost of such training shall be borne by the Government. The necessary space and workers shall be provided by the contractor and no claim what so ever shall be entertained.

Clause-19L

Contribution of EPF & ESIS

Applicable

Clause-20

Minimum wages act to be complied with

Applicable

Clause 21

Work not to be subcontracted. Action in case of insolvency

The contract shall not be assigned or sublet without the written approval of the Engineer-in-Charge. If the contractor shall assign or sublet his contract, or attempt to do so, or become insolvent or commence any insolvency proceedings or make any composition with his creditors or attempt to do so, or bribe, gratuity, gift, loan, perquisite, reward or advantage pecuniary or otherwise, or any benefit, directly or indirectly, be given, promised or offered by the contractor, or any of his servants, agents, employees, officers or person in the employ of Government in any way relating to his office or business, or any such officer or person shall become in any way directly or indirectly interested in the contract, the Engineer-in-Charge on behalf of the President of India shall have power to adopt the course specified in the said Clause 3 shall ensure.

Clause 25 Settlement of Dispute by Conciliation and Arbitration

- (i) **Conciliator** -
-
- (ii) **Arbitrator Appointing Authority** -
-
- (iii) **Place of Arbitration** - **Group Centre CRPF Guwahati, Assam-781023**
-

Action where no Specifications are specified

In the case of any class of work for which there is no such specifications as referred in the above clause, the work shall be carried out in accordance with the Bureau of Indian Standards Specifications. Where there are no such specifications in Bureau of Indian Standards, the work shall be carried out in accordance with the manufacturers' specifications, if not available then as per state/ District Specifications. Where there are no such specifications as required above, the work shall be carried out in all respects in accordance with the instructions and requirements of the Engineer-in-Charge.

Water for Work The contractor(s) shall make his/their own arrangements for water required for the work. Extra will be paid for the same. This will be subject to the following conditions.

- i. That the water used by the contractor(s) shall be fit for construction purposes of the Engineer-in-Charge.
- ii. The Engineer-in-Charge shall make alternative arrangements for supply of water at cost of contractor(s) if the arrangements made by the contractor(s) for procurement in the opinion of the Engineer-in-Charge, unsatisfactory.
- iii. **WATER CHARGES**: - If water is used from CRPF campus then 1% amount of cost shall be levied from contractor.
- iv. **ELECTRICITY CHARGES**: - If electricity is provided by CRPF campus then cost shall be levied on contractor.

Hire of Plant & Machinery

The contractor should be the owner of all the machinery and plants being used in which tender has been called for

Clause Applicable
33, 34
& 35

**No Gaze
tted En
gineer t
o work
as Cont
ractor w
ithin on
e year o
f retire
ment**

No Engineer of Gazetted rank or other Gazetted officer employed in engineering or in an engineering department of the Government of India shall work as a contractor for a period of one year after his retirement from government service without the permission of Government of India in writing. This contract is liable to be cancelled if or any of his employees is found at any time to be such a person who had not obtained the permission of Government of India as aforesaid, before submission of the tender or engagement for the work, as the case may be.

Sd/- 12-07-2026
LT. COLONEL ANAND KUMAR

COMDT

Contract Cell, NEZ HQr
[For and on behalf of the President of
India]

INTEGRITY PACT

To,

Commandant (Engr),
Contract Cell, NEZ HQr
Guwahati, Assam

Sub: Submission of Tender for the work of.....

Dear Sir, I/We acknowledge that CRPF is committed to follow the principles thereof as enumerated in the Integrity Agreement enclosed with the tender/bid document.

I/We agree that the Notice Inviting Tender (NIT) is an invitation to offer made on the condition that I/We will sign the enclosed integrity Agreement, which is an integral part of tender documents, failing which I/We will stand disqualified from the tendering process. I/We acknowledge that THE MAKING OF THE BID SHALL BE REGARDED AS AN UNCONDITIONAL AND ABSOLUTE ACCEPTANCE of this condition of the NIT.

I/We confirm acceptance and compliance with the Integrity Agreement in letter and spirit and further agree that execution of the said Integrity Agreement shall be separate and distinct from the main contract, which will come into existence when tender/bid is finally accepted by CRPF. I/We acknowledge and accept the duration of the Integrity Agreement, which shall be in the line with Article 1 of the enclosed Integrity Agreement.

I/We acknowledge that in the event of my/our failure to sign and accept the Integrity Agreement, while submitting the tender/bid, CRPF shall have unqualified, absolute and unfettered right to disqualify the tenderer/bidder and reject the tender/bid in accordance with terms and conditions of the tender/ bid.

Yours faithfully

(Duly authorized signatory of the Bidder)

To be signed by the bidder and same signatory competent / authorized to sign the relevant contract on behalf of CRPF.

INTEGRITY AGREEMENT

This Integrity Agreement is made at..... on thisday of 20.....

BETWEEN

President of India represented through **DIG, Group Centre CRPF Guwahati, Assam-781023**.....(Name of Zone) CRPF, (Hereinafter referred as the (Address of Office) 'Principal/Owner', which expression shall unless repugnant to the meaning or context hereof include its successors and permitted assigns)

AND

.....
.....
(Name and Address of the Individual/firm/Company) through (Hereinafter referred to as the (Details of duly authorized signatory) "Bidder/Contractor" and which expression shall unless repugnant to the meaning or context hereof include its successors and permitted assigns)
Preamble

WHEREAS the Principal / Owner has floated the Tender (NIT No.....) (hereinafter referred to as "Tender/Bid") and intends to award, under laid down organizational procedure, contract for.....
(Name of work)
hereinafter referred to as the "Contract".

AND WHEREAS the Principal/Owner values full compliance with all relevant laws of the land, rules, regulations, economic use of resources and of fairness/transparency in its relation with its Bidder(s) and Contractor(s).

AND WHEREAS to meet the purpose aforesaid both the parties have agreed to enter into this Integrity Agreement (hereinafter referred to as "Integrity Pact" or "Pact"), the terms and conditions of which shall also be read as integral part and parcel of the Tender/Bid documents and Contract between the parties.

NOW, THEREFORE, in consideration of mutual covenants contained in this Pact, the parties hereby agree as follows and this Pact witnesses as under:

IN WITNESS WHEREOF the parties have signed and executed this Integrity Pact at the place and date first above mentioned in the presence of following witnesses:

.....
(For and on behalf of Principal/Owner)

.....
(For and on behalf of Bidder/Contractor)

WITNESSES:

1..... (signature, name and address)

2..... (signature, name and address)

Place:

Dated :

ADDITIONAL TERMS AND CONDITIONS

1. PAYMENT: -

- a. Works are required to be executed on credit basis only and payment will be released after submission of RA bill by the contractor and scrutiny by the department.
- b. Payment in advance or immediately cannot be made.
- c. The Payment action will be processed on production of the following documents:
 - Bill in Triplicate.
 - A Copy of award of work.
 - A copy of Certificate issued by **DIG Group Centre CRPF Guwahati, Assam-781023** in consultation with Engineer-in-charge that contracted work for the period for which payment has been claimed, has carried out by the contractor satisfactory.

d. GST/TDS/GST-TDS/ Labour Cess and other taxes will be deducted from the Bill of Contractor by RPAO as per norms. EPF & ESIC shall be reimbursed by RPAO only on submission of proof of payment by contractor to concerned authorities.

e. Contractor may claim RA Bills at interval of 30 days for the work done as measured and entered in measurement book. RA bill should be checked by Insp/SI (Civil) & Engineer-in-charge and countersigned by Estate Officer before release of payment. Security Deposit of 2.5% shall be retained from the Work Done in the RA Bill which will be paid after completion of Defect Liability Period.

1. **MEASUREMENT:** Entire work done at Site shall be recorded in measurement book duly signed by Contractor & Insp/SI (Civil) & AC(Engr). Measurements in measurement book shall be recorded jointly by contractor/authorized representative of contractor and Insp/SI Civil and 50% MB checked & signed by AC(Engr) before processing bill to Estate Officer for counter sign.

2. **COMPLETION CERTIFICATE:** Upon Completion of Work, Contractor shall intimate Estate Officer in writing of completion of work. If Estate Office is completely satisfied with the work, he shall issue Completion Certificate duly signed by Engineer-in-Charge (AC Engr) within 20 days of intimation of contractor. If Minor Defects Persists, Provisional Completion Certificate can be issued subject to rectification of defects brought out by Estate Officer. A suitable time frame for rectification of such defects shall also be intimated by Estate Officer in writing beyond which Comdt (Engr), NEZ Hqr shall be empowered to rectify the defects through other agency at risk and cost of the contractor. This period shall not be less than 30 days and should not exceed 180 days in any case from the date of intimation of defects. Such defects list shall be made part of Provisional Completion certificate by Estate Officer.

3. **DISPUTE IN CONTRACT:-** In case of any ambiguity in the provisions of the Contract Agreement, Decision of Accepting Officer shall be Final & Binding on the Contractor. **GCC construction works-2023 with upto date** correction slips will prevail and applicable.
4. All materials required to be used on works shall be got approved from the Engineer-in-charge in advance. In case of doubt on any material, Engineer-in-charge has right to get the material tested from any Govt. approved labs/NABL and the charges for the same shall be borne by the contractor, upto the overall amount of Rs. 02 lakh in entire work. Beyond Rs. 02 lakh, the cost of such test shall be borne by the contractor if sample fails in the test & by CRPF if sample passes the test.
5. The quoted rate should be inclusive of all taxes, levies, works contract taxes, duties etc.
6. All items to be used in this work should be branded and ISI certified. In this case CPWD approved list of material for similar work may be followed. If any make is not specified, decision of Engineer-in-charge shall be final and binding.
7. Payment to contractor shall be released only after submission of purchase voucher of all new items.
8. **TERMINATION OF CONTRACT:** - In case of violation/breach of any agreed terms and conditions of contract and persistently failure/negligence to observe and perform all or any of the acts, deeds, matters or things to be observed and performed by the Contractor. Tender Accepting Authority may cancel/Terminate this contract and the performance security deposit will be forfeited.
9. **CONFLICT OF INTEREST:** - The bids of any tenderer may be rejected if a conflict of interest between the bidder and CRPF is detected at any stage. Tender Accepting Authority reserves the right to accept or reject the tender without assigning any reason whatsoever.
10. Conditional tender is not acceptable and will be summarily rejected.
11. **DEFECT LIABILITY PERIOD:** - Defect liability period is 01 year, which will be reckoned from the date of final and complete handing/taking over of building/infrastructure. If any defects occurs/noticed during this period, then a notice in this regard will be issued to the contractor and it is the responsibility of contractor to rectify/repair the defects at his own cost. The work must be got started by the contractor within 15 days after receipt of the 1st notice. If the contractor is unable or unwilling to repair the defects, the competent authorities reserves full rights to forfeit the security deposit and may blacklisted/debarred the firm and rectify the defects at risk and cost of the contractor. Any amount on this account due to the department shall be recovered from the Contractor.
12. Payment for execution of electrical works will be done only after inspection by the BOO/electrical engineer of State Electrical Department/any Govt. electrical engineer(serving) detailed by Estate Officer/Engineer-in-charge. A completion certificate is required to be submitted by the BOO/electrical engineer of State Electrical Department/any Govt. electrical engineer (serving). Any charges if occurs that will be borne by the contractor. No payment in this regard will be done by the CRPF.
13. All credit obtained during dismantling shall be deposited with CRPF.

LIST OF MAKES

MATERIALS: Unless specific makes/manufacturers are specified in the tender documents all the materials to be procured by the contractor for incorporation in the work under this contract (with the exception of local materials like bricks, stone aggregate, stones, sand etc) shall be with ISI certifications mark.

SAMPLES OF MATERIALS: The contractor shall produce samples of all materials and shall obtain approval in writing from Engineer-in-charge before he places bulk order for the materials for incorporation in the work. The contractor shall not procure materials unless the samples are first got approved from the Engineer-in-charge .

TESTING : The contractor shall submit the manufacturer's test certificate in original along with the Test Sheet giving the result of each physical test as applicable and the chemical composition of the cement or authenticated copy thereof, duly signed by the manufacturer with each consignment clearly bringing out lot No. The Engineer-in-Charge shall record these details in the Cement Supply & Acceptance register

Following mandatory tests shall be carried out for cement procured by the Contractor:

- i. Initial and final setting time
- ii. Soundness test
- iii. Compressive strength test at 3, 7 & 28 days as specified in relevant IS code.

CONCRETE

MATERIALS FOR CONCRETE:-

- **LIME:** Lime shall be eminently hydraulic lime (Class 'A') and shall conform to IS:712.
- **CEMENT:** Cement shall be stored in dry a place covered all round and no stacks shall be more than 15 bags high.
- **COARSE AGGREGATE:** Coarse aggregate shall be crushed stone aggregate and shall conform to standard specifications followed in the industry.
- Raw material source to be approved by the Engineer-in-Charge.

APPROVED MAKES OF MATERIALS

Approved makes of materials to be used in the work are as given in the table enclosed. In case of non-availability of these makes, the Engineer-in-charge may allow use of alternative makes. Only BIS marked materials shall be used in the work. Non-BIS marked materials may be permitted by the Engineer-in-charge only when BIS marked materials are not manufactured.

LIST OF APPROVED MANUFACTURERS AND MAKES

SL NO.	NAME OF PRODUCT	MAKES/BRANDS/MANUFACTURERS
1.	ORDINARY PORTLAND CEMENT	J.K., ACC, AMBUJA, BIRLA
2.	REINFORCEMENT BARS	TATA STEEL (TISCON), SAIL (EQR/ SEQR), RINL, JINDAL (JSW NEOSTEEL/PANTHER)

3.	EXPANSION JOINTS	J. SONGS, METCO, SANFIELD (INDIA) P LTD. Z-TECH (INDIA) PVT. LTD.
4.	ADMIXTURES FOR CONCRETE	FOSROC, SIKA, MBT, ASIAN LABORATORIES DURA BUILD CARE, BASF, FEVICOL, CICO TECHNOLOGIES LTD
5.	STRUCTURAL STEEL	TATA, SAIL, RINL. ISCO, SRMB
6.	WELDING ELECTRODES	ESAB, ADVANI-ORLIKON, WELDALLOY
7.	WATER PROOFING	SIKA, PIDILITE, ASIAN PAINTS, FOSROC
8.	SYNTHETIC ENAMEL PAINT	JICI (SUPER GLOCE), NEROLAC, BERGER (LUXOL), JENSONS AND NICHOLSON, ASIAN PAINTS (APCOLITE). CICO, MBT, FOSROC
9.	ANTI CARBONATION PAINTS	CICO, MBT, FOSRO
10.	THERMOPLASTIC PAINTS	CBM, CMS, RELIANCE THERMOPLAST
11.	RMC	RMC, ACC, BIRLA, L&T AND OTHER REPUTED MANUFACTURE OF RMC SUBJECTED TO APPROVAL OF ENGINEER-IN-CHARGE
12.	TMT FE 415/500	TISCON, ISCON, RINL, SAIL, JINDAL
13.	WHITE CEMENT	BIRLA WHITE, J.K. WHITE
14.	PUTTY	BIRLA, J.K. PUTTY OR EQUIVALENT.
15.	WASH BASIN	PARRYWARE, CER, JAQUAR.
16.	CLEAR GLASS	MODI GUARD, SAINT GOBAIN, AIS
17.	G.I. PIPES	TATA STEEL TUBES, JINDAL, PRAKASH, SURYA
18.	G.I. FITTINGS	UNIK, KS, AMCO, AVR, NVR, RR
19.	HUBLESS CENTRIFUGALLY CAST IRON SPUN PIPES & FITTINGS IS:151205	NECO, HEPSCO OR EQUIVALENT.
20.	DI PIPES & FITTINGS	KESORAM, ELECTROSTEEL OR EQUIVALENT
21.	CP BRASS FITTINGS	PARRYWARE, JAQUAR, CERA
22.	BRASS STOP & BIB COCK	ZOLOTO, SANT, L&T, LEADER, CERA
23.	ALUMINIUM SECTIONS (ANODISING BY ANODIZING FIRM) APPROVED	HINDALCO, JINDAL, INDIAN ALUMINIUM CO. OR AS APPROVED BY ENGINEER-IN-CHARGE
24.	STAINLESS STEEL KITCHEN SINK	NIRALI, JAYNA, PRAYAG, JINDAL
25.	PLASTIC W.C. SEAT COVER	PARRYWARE, HINDWARE, CERA
26.	UPVC WINDOW	FENESTA, EWIN, REHAU
27.	PVC TANKS	SINTEX, SUPREME, ASTREL-3 OR LAYERED MORE ISI MARKED
28.	MIRROR GLASS	ATUL, SAINT GOBAIN, MODI GUARD, HNG, CERA
29.	CP WASTE & FLUSH PIPES	AS APPROVED BY ENGINEER-IN-CHARGE.
30.	PVC FLUSHING CISTERN.	PARRYWARE, HINDWARE, JOHNSON, CERA
31.	TILE FIXER / ADHESIVE	AS APPROVED BY ENGINEER-IN-CHARGE.
32.	VENEERED PARTICLE BOARD	NOVAPAN, KITPLY, ANCHOR, NATIONAL, ARCHIDPLY, CENTURY PLY
33.	LAMINATED PARTICLE BOARD / LAMINTAES	NOVAPAN, KITPLY, NATIONAL, ARCHIDPLY, CENTURY PLY, ECOBOARD.
34.	FLUSH DOOR SHUTTERS	DURO, ARCHIDPLY, KUTTY FLUSH DOOR, KITPLY INDUSTRIES (SWASTIK), CENTURY PLY. OR AS APPROVED BY ENGINEER-IN-CHARGE
35.	FACTORY MADE PANELLED & WIRE GAUGE WOODEN DOOR/ WINDOW SHUTTERS	AS APPROVED BY ENGINEER-IN-CHARGE
36.	STEEL WINDOWS / PRESSED STEEL FRAMES	AS APPROVED BY ENGINEER-IN-CHARGE.
37.	M.S PIPE	TATA, JINDAL, BHUSHAN INDUSTRIES, PRAKASH STEEL TUBES, OR AS APPROVED BY ENGINEER-IN-CHARGE
38.	PVC PIPE & FITTINGS	SUPREME, AKG, FINOLEX, PRINCE, SFMC
39.	ACRYLIC DISTEMPER	NEROLAC, BERGER (BISION ACRYLIC) ASIAN PAINTS (TRACTOR ACRYLIC) IST

40.	DRY DISTEMPER	QUALITY, DULUX WEATHER SHIELD, ICI BERGER (CASTLE), JENSON & NICHOLSEN(J&N)
41.	STEEL PRIMER	ICI, NEROLAC, BERGER, ASIAN PAINTS. IST QUALITY
42.	WOOD PRIMER	ICI, NEROLAC, BERGER, ASIAN PAINTS. IST QUALITY
43.	MOSAIC TILES / CHEQUERED TILES	HINDUSTAN, JONSON, NITCO, MODERN, NTC, A1
44.	CERAMIC WALL TILES	KAJARIA, SOMANY, JOHNSON, AGL, VERMORA
45.	DASH / ANCHORING FASTENERS	HILTI / FISCHER OR EQUIVALENT
46.	NUTS / BOLTS & SCREWS	GKW, ATUL OR EQUIVALENT
47.	FLOAT VALVE	LEADER, PRAYAG, ZOLOTO, L&T
48.	CP FITTINGS/MIXER PILLAR TAPWASHERS	JAQUAR, HINDWARE, PARRYWARE, CERA
49.	CP ACCESSORIES	JAQUAR, HINDWARE, PARRYWARE, CERA
50.	C.I SLUICE VALVES & REFLEX VALVES GUN METAL GATE VALVES, GLOBES	LEADER, ZOLOTO, SANT, KIRLOSKER, L&T
51.	STONE WARE PIPES & GULLY TRAPES	PERFECT, HIND OR ISI MARKED S.W PIPES OR AS APPROVED BY ENGINEER-IN-CHARGE
52.	GLAZED FIRE CLAY KITCHEN SINK	PAMINI, SANFIRE, RKCP OR AS APPROVED BY ENGINEER- IN- CHARGE
53.	VITRIFIED TILES	JOHNSON, AGL, VARMORA, KAJARIA, SOMANY
54.	WATER METER	PRIMA (ISI), KRANTI, DASHMESH OR BIS MARKED PRODUCT
55.	GROUTING COMPOUND	ENDURA, PIDILITE OR AS APPROVED BY ENGINEER-IN-CHARGE
56.	GLASS MOSAIC TILES	ITALIA, OPIO OR AS APPROVED BY ENGINEER-IN-CHARGE
57.	PAVER BLOCKS & CURVE STONES	NITCO PREFEB, ULTRA KK, TERRAFIRMA, UNISTONE, UNITILE, NTC, ISI MARKED
58.	GLASS MOSAIC TILES	ITALIA, OPIO OR AS APPROVED BY ENGINEER-IN-CHARGE
59.	NON RETURN VALVE (CHECK VALVE) 1/2" TO 1/4"	KALSI PUMP PVT. LTD, ZOLOTO, SAKARAL, UNIK OR BIS APPROVED PRODUCTS.
60.	LINE FILTER VALVE 1/2" TO 2"	KALSI PUMP PVT. LTD OR BIS APPROVED PRODUCTS.
61.	FERRULES 15 MM, 20MM & 25MM	DHAWAN SANITARY UDYOG (PRIMA) OR BIS APPROVED PRODUCTS
62.	STAINLESS STEEL STAIRCASE RAILING	JINDAL S S LTD, ICICH INDUS, ESSAL, DORMA OR AS APPROVED BY ENGINEER-IN-CHARGE
63.	LOCKS/LATCH/FITTINGS	GODREJ, HARRISON, YALE, DORMA
64.	HYDRAULIC DOOR CLOSER / FLOOR SPRING	HARDWYN, GODREJ, GRACE, EVEREST, DORMA
65.	FIRE CHECK DOOR	NAVAIR, ROMAT, KUTTY DOOR
66.	ANODISED ALUMINUM HARDWARE (HEAVY DUTY)	HARDIMA, EVERITE, SIGMA (ISI MARKED), DORMA
67.	TEMPERED GLASS	MODI FLAT & SAINT GOBAIN, ASHAHI
68.	POLYESTER POWDER COATING SHADES	NEROLAC, BERGER, J&N
69.	FRICTION STAY HINGES	EARL-BIHARI OR AS APPROVED BY ENGINEER-IN-CHARGE
70.	NUTS, BOLTS AND SCREWS, STEEL	KUNDAN PRIYA ATUL OR AS APPROVED BY ENGINEER-IN- CHARGE
71.	EPDM GASKET	HANU / ANAND OR AS APPROVED BY ENGINEER-IN-CHARGE
72.	STRUCTURAL SILICON	DOW CORNING / WACKER OR EQUIVALENT
73.	WEATHER SILICON	DOW CORNING / WACKER OR EQUIVALENT
74.	COPPER TUBES / PIPES	RAJCO, MAX FLOW ABC OR EQUIVALENT
75.	COPPER FITTINGS	YORKSHINE, IBP, BCONEX
76.	U-PVC PIPE	FLOW GUARD, FINOLEX, ASTRAL
77.	C-PVC PIPE AND FITTINGS	ASTRAL, ASHIRVAD, PRINCE HEAVY DUTY, FINOLEX
78.	CEMENT BASED PAINT	M/S SNOWCEM INDIA LTD, ASIAN, BURGER,

79.	ALUMINUM SLIDING DOOR BOLT, TOWER BOLT HANDLE.	NEOXE AND AODI. OR AS APPROVED BY ENGINEER-IN- CHARGE
80.	VITREOUS CHINA SANITARY WARE	PARRYWARE, NEYCER, CERA, HINDWARE
81.	CENTRIFUGALLY SAND CAST (SPUN) IRON PIPES	NECO OR ANY OTHER AND FITTINGS B.I.S MARKED PRODUCT, BABULAL BAJAJ IRON FOUNDRY MATHURA (HIF) OR BIS APPROVED PRODUCTS
82.	CENTRIFUGALLY CAST (SPUN) PIPE	ELECTRO STEEL, KESORAM (CLASS LA) OR EQUIVALENT
83.	APP SHEET	SALIMAR, DR FIXIT, SIKKA OR AS APPROVED BY ENGINEER- IN- CHARGE
84.	PVC DOOR SHUTTER & FRAME	SINTEX, RAJSHRI OR EQUIVALENT AS APPROVED BY ENGINEER-IN-CHARGE
85.	PRE-COATED PROFILE SHEET	TATA, JSW OR EQUIVALENT
86.	HDF LAMINATED BOARD	ACTION TESA, CENTURY OR AS APPROVED BY ENGINEER- IN- CHARGE
87.	BITUMEN	HPL, COAL INDIA, IOCL OR AS APPROVED BY ENGINEER-IN- CHARGE
88.	ACP SHEET	REYNOBOND, VIRGO ACP, ALEX PANELS, ALUDECOR OR AS APPROVED BY ENGINEER-IN- CHARGE
89.	LED LIGHT FITTING & LUMINARIES FOR ROAD AND STREET LIGHTING (OUT DOOR)	WIPRO, C&S ELECTRIC, PHILIPS, CROMPTON, BAJAJ, OSRAM
90.	LED LAMPS	WIPRO, PHILIPS, CROMPTON, BAJAJ, OSRAM
91.	SMART STREET LIGHTS AND CONTROL SYSTEM	ORIENT ELECTRIC LTD, OPULUS
92.	STREET LIGHT FITTING & ACCESSORIES -HPSC (70/ 150/ 250/ 400) HPMV (80/ 125/ 250/ 400)	POLYCAB, PHILIPS, C&S ELECTRIC, SURYA, WIPRO
93.	SOLAR STREET LIGHT FITTINGS	JILCO, PHILLIPS, OSRAM
94.	STREET LIGHT TIMERS	SINETRAC, INDO ASIAN, HAVELLS
95.	CI PIPES & FITTINGS	JINDAL, TATA METALIKS, TATA KUBOTA
96.	INTERLOCKING TILES/ PAVER BLOCKS	ISI MARKED GLOSSY FINISH
97.	DECORATIVE PAINT (EXT & INT)	SNOWCEM, ASIAN, BERGER, DULUX
98.	CHAIN LINK FENCING / BARBED WIRE / PUNCHED TAPE CONCERTINA COIL / RAZOR BLADE TAPE FENCING	A-1 FENCE, ARMOSTRONG WIRES, MAIMOM ROGER
99.	GALVALUME SHEET	TATA BLUE SCOPE, JSW, BHUSHAN, VARDHMAN
100.	CHROMIUM PLATED BATHROOM FITTINGS OF CP, CAST COPPER ALLOY FANCY TYPE BIB TAP, STOP VALVES AND PILLAR TAP, SANITARY FITTINGS, SHOWER PNAEL	JAQUAR / KOHLER / ROCA / GROHE
101.	VITREOUS CHINA WC / WHB / URINAL / SOAP DISH / URINAL PARTITION WALL / LABORATORY SINK	PARRYWARE / CERA / JAQUAR
102.	NON ASBESTOS FIBRE CEMENT BOARDAS PER IS 14862	ARMSTRONG / SAINT GOBAIN (GYPROC) / EVEREST / INDIA GYPSUM/
103.	ACRYLIC EMULSION / WEATHER PROOF PAINT	ASIAN PAINTS (ROYAL) / BERGER (LUXOL SILK SPLENDER)/ ICI (DULUX VELVET TOUCH)
104.	PLASTIC EMULSION PAINT	ACROCEM / DUROCEM / SUPER SNOWCEM / BERGER / ASIAN PAINT (GUTUCAM)
105.	HOUSE WIRING CABLE (1100 VOLTS)/CABLE FOR SERVICE CONNECTION/CABLE FOR PANEL BARD WIRING	POLYCAB, RR KABEL, FINOLEX, RPG

106.	PIANO SWITCHES/sockets ETC.	ISI MARKED PRODUCTS OF LEGRAND/CRABTREE/
107.	PVC CASING CAPPING /CONDUIT	IAQUAR/SCHNEIDER/PHILLIPS (MODULAR TYPE) FINOLEX / MODI / PRESTO PLAST / PLAZA / KALINGA/ RICHIA
108.	WIRING ACCESSORIES AND FITTINGS	ANCHOR / LEGRAND/ KINJAL (ISI MARKED)/ RICHIA
109.	MCBS, DBS, ISOLATOR	LEGRAND /SIEMENS/ SCHNIEDER/ABB.
110.	MCCB	ABB/ LEGRAND/ SCHNEIDER/SIEMENS
111.	LT UG /SERVICE CABLE	POLYCAB/FINOLEX/KEC
112.	EXHAUST FAN/CEILING FAN	CROMPTON GREAVES/KHAITAN/BAJAJ/HAVELLS/ORIENT
113.	HEATER WATER STORAGE TYPE ELECTRIC GEYSER	CROMPTON GREAVES /BAJAJ/HAVELLS
114.	FALSE CEILING	ARMSTRONG/ EVEREST/GYPROC
115.	EPOXY PAINT	NEROLAC OR EQUIVALENT
116.	CC KERB STONE	NITCO PREFAB, K.K. MANHOLE, TERRAFIRMA, UNISTONE.
117.	MILD STEEL TUBES	TATA, SAIL, ISCO, SRMB
118.	APP MEMBRANE	ASIAN PAINTS/FOSROC/SIKA/STP
119.	GLOW STUD	TATA BP/3M India orEquivalent

Remarks:-

- Buyer/ estate officer shall ensure the preference and choice any brand as suggested above after award of tender.
- The contractor shall remain fully responsible for quality, warranty, and performance of materials used, irrespective of approved brand.
- Any change in the brands mentioned above and elsewhere shall be allowed only after approval of the Engineer-in-charge.

PARTICULAR SPECIFICATIONS

GENERAL

Work under this contract shall be carried out in accordance with Specifications, drawings, General Specifications and other provisions contained in CPWD Manuals and Specifications General Rules, specifications, special conditions and all preambles in the CPWD Schedule shall be deemed to be applicable to the work under this contract, unless specifically stated otherwise in these documents and in case of any conflicting provisions in CPWD schedule and in these tender documents, the provisions in these documents shall take precedence over the aforesaid provisions in the CPWD Schedule. The term "as specified" wherever appears in the tender documents and drawings, relates to relevant particular specifications and in its absence, general specifications. Where specifications for any item of work are not given in CPWD Schedule or in these particular specifications, specifications as given in relevant Indian Standard Code of Practice shall be followed. Unit rate quoted by the tenderer shall be deemed to include for any minor details/items of work and/or constructions which are obviously and fairly intended and which may not have been included in these documents but which are essential for the execution and entire completion of work. Decision of the Accepting Officer as to whether any minor detail of work and/or construction is obviously and fairly intended to be included in the contract or not, shall be final, conclusive and binding.

LOCAL MATERIALS:

Irrespective of actual distance involved, local materials such as stones, aggregates, sand, road metals etc shall conform to or superior to the specifications given here in after and to the samples kept in the office of Executing Officer. The tenderers are advised to inspect these samples. The tenderers shall be deemed to have inspected the samples and have full knowledge thereof whether they inspect them or not before quoting their tender.

SAMPLES OF MATERIALS: -

- a. Specific requirements regarding dimensions, strength, weight and finishes, as per IS, CPWD Specification and the particular specifications given hereinafter vis-à-vis actual properties check, tests carried out, reference to test certificates and markings, etc based on which samples of each materials are approved as Conforming to relevant specification shall be recorded in the sample approval register.
- b. The contractor shall produce samples of all materials and shall obtain approval in writing from Engineer-in- charge before he places bulk order for the materials for incorporation in the work. The contractor shall not procure materials unless the samples are first got approved from the Engineer-in-charge.
- c. Samples of approved materials shall be kept in custody of Engineer-in-Charge till completion of work.

RECORD OF MATERIALS

- a. The quantity of all the proprietary materials (including materials and quantity of which cannot be checked after incorporation in the works) shall be recorded in measurement books and signed by the Contractor, the Engineer-in- Charge and Insp/SI (Civil) as a check to ensure that the required quantity has been brought at site for incorporation in the work.
- b. Materials brought to site shall be stored as directed by the Engineer-in-Charge and shall be suitably marked for identification.
- c. The contractor shall procure all the materials (where specific makes/manufacturer's specified) directly from their manufacturers or from their authorized dealers only. The contractor shall ensure that the materials are brought to site in original sealed containers/packing bearing manufacturers marking except in the case of the requirement of material(s) being less than smallest packing.
- d. The contractor shall produce to Engr-in-charge original printed and machine numbered purchase vouchers/invoices including manufacturer's test certificate (where applicable) for all the materials mentioned. Copies of orders placed on the manufacturer/authorized dealers shall also be provided by the contractor to Engr-in-Charge along with above documents. Whenever procured and brought to site of work for incorporation in the work, a Xerox copy of such vouchers/invoices shall be stamped (office stamp) and defaced in ink by the Engineer-in-Charge & Insp/SI (Civil) stating verified for materials purchased and brought to the site of work for incorporation in the subject work and signed with date before allowing payment for these materials through RA Bills.

STANDARD OF WORKMANSHIP

To determine the acceptable standard of workmanship and fittings, wiring etc, the Engr-in-charge shall order the contractor to execute certain typical portion of work (different trades) and services sufficiently in advance of other work. These shall be executed and completed under the close supervision of the Engineer-in-charge and Insp/SI(Civil).

On approval by the Engineer-in-charge of such items, these items shall signed and/or suitably identified by the Engineer-in-charge and labeled as guiding samples. The record of such inspection and passing of each stage of these samples shall be recorded by Engineer-in-charge under his dated signatures. Work on such sample shall be progressed well ahead (minimum two stages ahead). Approved finishes/workmanship shall be followed in the work as a whole.

TESTING OF CEMENT

The Engr-in-charge shall also organize independent testing of random samples of

cement (both physical and chemical properties) drawn from various lots for each consignment to cement brought out by the contractor before incorporation in the work from the National Test House, SEMT, Regional Research Laboratories, Government approved laboratories, as per IS: 3535 (Method of sampling Hydraulic cement), IS: 4031 (Method of physical test for Hydraulic Cement) and IS: 4032 (Method of chemical analysis of Hydraulic cement.) The cement shall conform to chemical requirements and physical requirements as specified in respective IS. The tests carried out as per provisions of IS codes specified herein before shall be the criteria for acceptance of cement by Engr-in-Charge & Insp/SI(Civil). If samples from a lot/lots are not within the acceptance limits of Indian standard the lot/lots shall be rejected without any claims or compensation to the contractor for the lot/lots purchased. The contractor shall replace the lot/lots with the fresh one, which shall be tested again for acceptance. The cost of all tests carried out on cement before acceptance for incorporation in the work shall be borne by the contractor whether the results are acceptable or not.

STORAGE

Cement shall be stored over dry platform at least 20cm high in such a manner as to prevent deterioration due to moisture or intrusion of foreign matter. In case of store rooms, the stock should be at least 20cm above from floors and 60 cm away from walls in addition to precautions specified in Works Manuals. Inspections shall be carried out once a day by the Engineer-in-Charge & Insp/SI(Civil). It shall be ensured by the Engineer-in-Charge that tested and untested cement are segregated and stored separately with distinct identification. The cement Godown shall be provided with two locks on each door. The key of one lock at each door shall remain with the Engineer-in-Charge or his representative and that of the other lock with the contractor's authorized representative at site of works so that cement is removed from the Godown only according to daily requirement with the knowledge of both the parties.

DOCUMENTATION

The contractor shall submit original vouchers from the supplier for the total quantity of cement supplied under each consignment to be incorporated in the work. All consignments received at the work site shall be inspected by Engr-in-charge & Insp/SI(Civil) along with the relevant documents before acceptance. The original vouchers and the Test Certificates shall be defaced by the Engineer-in-Charge & Insp/SI(Civil) and kept on record duly authenticated and with cross-reference to the control number in the cement Supply & Acceptance Register. The cement supply & Acceptance Register will be signed by Insp/SI(Civil), Engineer-in-Charge and the Contractor. The Accepting Officer may order a Board of Officers for random check of cement and verification of connected documents. The entire quantity of all types cement shall also be suitably recorded in the Measurement Book for record purpose not to be abstracted before incorporation in the work and shall be signed by the Engineer-in-Charge, Insp/SI(Civil) and the contractor.

SCHEDULING OF SUPPLY

Schedule of procurement of cement shall be finalized by the contractor with Engr-in-charge and shall be incorporated in the CPM chart so that procurement is in accordance with the progress contemplated in the CPM prepared. The complete requirement of cement shall be worked out before making any RA Bill payment and procurement of cement by the contractor shall be completed sufficiently in advance of the execution of work.

SAND(Coarse & Fine)

Sand for all concrete work shall be river sand (from near area or any other Sand) conforming to samples, complying with the requirement as specified in CPWD. Sand in the zone II grading may also be permitted provided mix design is done and the requisite strength of the concrete is achieved.

Note: Sample of sand shall however, be got approved from the Engr-in-charge & Insp/SI(Civil) before incorporation in the work. Other provisions in the respective clauses shall remain unchanged.

CONCRETE MIX

All mixes of concrete and mortar mentioned in this tender document shall be by volume except design mix concrete conforming to IS-456 for which all the ingredients are proportioned and mixed by weight.

WATER BOUND MACADAM (WBM)

WBM shall consist of consolidated thickness as per schedule of broken/crushed

stone (granite, trap or basalt stone aggregate). Stone shall be hard and durable and shall be free from excess of flat and elongated, soft and disintegrated particles, dirt and other objectionable matter. Stone aggregate shall be grading 2 (63 to 45 mm size) as given under CPWD Specifications & Manuals. Screening shall be of red Bajri/Mooram. Unless otherwise specified, the laying, compacting and rolling etc shall be as specified in CPWD Works Manual & Specifications. Stone for WBM shall be laid out as specified in CPWD.

STEEL AND IRON WORK

General:- All items of steel which are required for the work under this contract shall be procured supplied and incorporated in the work by the contractor under his own arrangement.

Grades and Quality

Steel supplied by the contractor shall conform to the following grades and quality.
Structural steel

- i. Structural steel wherever mentioned shall be conforming to Fe 550 Gde conforming to IS-2062.
- ii. General purpose steel wherever mentioned shall be conforming E-165(Fe-290) conforming to IS-2062.

Source of Procurement

- a. Structural Steel : The Contractor shall procure all the structural steel from the main manufacturers.
 1. Rashtriya Ispat Nigam Ltd (RINL), Brand : "RINL"
 2. Tata Iron & Steel Company, (TISCO or Tata Steel), Brand : "TATA"
 3. Steel Authority of India Limited, (SAIL), Brand : "SAIL"
 4. M/s Jai Balaji Industries Ltd, Brand : "JAI BALAJI"
 5. M/s Shyam Steel Industries Ltd, Brand : "SHYAM TMT"
 6. M/s SPS Steel Rolling Mills Ltd, Brand : "ELEGANT TMT"
 7. M/s Steel Exchange India Ltd, Brand : "SIMHADRI TMT"
 8. M/s Jindal Steels and Power, Ltd, Brand : "JINDAL"
 9. M/s SRMB Srijan Ltd, Brand : "SRMB"
 10. M/s Concast Steel & Power Ltd, Brand : "CONCAST MAXX"
 11. M/s Adhunik Metaliks Ltd, Brand : "ADHUNIK MET +"
 12. M/s Shri Bajrang Power & Ispat Ltd, Brand : "GOEL TMT"
 13. M/s JSW Steel Ltd, Brand : "JSW TMT Plus"
 14. M/s Electro steel Steels Ltd., Brand : "ELECTROSTEEL"
 16. M/s Shyam Metalics& Energy Ltd , Brand : "SEL"
 17. M/s Kamachi Sponge & Power Corporation Ltd., Brand: "KAMACHI"
 18. M/s Electrotherm (india) Ltd Brand "ET TMT"
- b. The contractor shall within 15 days of placing of work order indicate the source for procurement of steel to Engineer-in-charge in writing.
- c. However, steel sections for railing, gates, fencing, guard bars, grills steel chowkats, hold fast etc, which do not constitute structural members, can be procured from main producers/secondary producer/BIS marked manufacturers or their authorized dealers at the option of contractor
- d. The contractor shall produce original vouchers from suppliers for the total quantity of steel purchased, under each consignment and be kept

on record by Engineer-in-Charge and authenticated.

Testing and Test Certificate

- a. The contractor shall produce manufacturers test certificate in original along with the test sheet giving the result of each mechanical test as applicable and the chemical composition of the steel supplied as specified in relevant IS Codes, duly signed by the manufacturer of their authorized dealers with each consignment.
- b. The original test certificate shall be kept on record in the office of Engineer-in-Charge (AC Engr).
- c. Independent testing of structural steel by the Engineer-in-Charge shall be mandatory in case of procurement from secondary producers and testing charges shall be borne by the Contractor irrespective of the outcome of test results.
- d. In both the cases at sub para (c) and (d) above, the contractor at his cost shall provide all facilities required for the testing and cost consumed in tests shall be borne by the contractor.

Minimum frequency of testing for each source and each consignment

- a. Structural Steel: -
 - i. Tensile test : One sample(3 specimen) for each test for every 25 tonnes or part thereof.
 - ii. Bend test : One sample(3 specimen) for each test for every 10 tonnes or part thereof.
- b. Steel for concrete reinforcement: -
 - i. Bar size less than 10mm : One sample(3 specimen) for each test for every 25 tonnes or part thereof.
 - ii. Bar size 10mm to 16mm (inclusive): One sample (3 specimen) for each test for every 35 tonnes or part thereof
 - iii. Bar size over 16mm: One sample (3 specimen) for each test for every 45 tonnes or part thereof.
- c. Bend test and tensile test for structural steel shall be carried as per IS-226 of 1975. For high strength deformed bar tensile, bend test and re bend test shall be done as per IS-1786 of 1985. For MS bars tensile and bend test shall be carried out as per IS 432 of 1982.
- d. Engineer-in-Charge has the right to get one more sample (3 specimen) tested if he is not satisfied with test result of the consignment.
- e. If the test results as per manufacturer's test certificate or of independent testing of random samples are not as per criteria laid down in the relevant BIS provisions, the entire consignment which is represented by the samples shall be rejected. Such rejected materials shall be removed and replaced by the contractor at his own cost forthwith.
- f. Cost of transportation of samples to the approved laboratory/test house and all testing charges shall be borne by the contractor.

Storage: - Steel supplied by the contractor shall be stored in accordance with the requirement of IS. Each grade and quality of steel shall be stored separately and have identification tags indicating the source, quality and grade.

Preservation and maintenance of steel: - The steel brought by the contractor shall be preserve do ensure that no rusting takes place till it is incorporated in the works.

Schedule of Supply :- The contractor shall procure the steel sections, timely as required in accordance with CPM Chart, agreed between Engr-in-charge and contractor. The contractor will forego his right to demand extension of time if the supply of steel got delayed due to his failure in placing order in time to the manufacturer/supplier.

Payment :- Payment shall allow after production of test certificate and original paid/purchase vouchers by the contractor.

Measurement

- a. The entire quantity of steel brought to site shall be recorded in measurement book as "NOT TO BE ABSTRACTED" indicating the reference to manufacturers, source of supply voucher number and test certificate before incorporation in the work and shall be signed both by the Engineer-in-Charge and the contractor. Proper documentation/record shall be maintained as per the instructions on the subject.

Normal waste and off cuts shall be stacked neatly which shall be the property of the Contractor. Contractor shall be allowed to remove such cut pieces after inspection and certifications by the Engineer-in-Charge.

Advance on account of payment made towards these cut pieces shall be recovered from advance on account of payment immediately falling due and before removal of such cut pieces from site.

Bending and fixing of bars for concrete reinforcement including mild steel wire for binding shall be carried out all as specified in CPWD. Binding wire for reinforcement shall be mild steel wire (annealed) of size not less than 0.9mm.

Steel supply/Acceptance form: - For each consignment of steel supply/acceptance form will be filled in and jointly signed by the department Rep. (Engineer-in-Charge/SI civil/Insp Civil) and contractor and accepted/rejected by Engineer-in-Charge before incorporation in the works.

Steel Reinforcement: - Reinforcement shall be fabricated, placed in position all as specified in CPWD specifications.

Guard Bars/Grills: MS Guard bars/grills wherever applicable and as indicated shall be provided to wooden/steel windows/ventilators as per details shown on drawings/schedule. Steel Guard bars/ steel grills shall be painted with 2 coats of synthetic enamel paint over a coat of primer as specified here-in-after.

Hold Fast/Lugs: Flat iron hold fast/lugs shall be provided by welding as and where shown on drawings except those, to be provided to wooden chowkats, which shall be fixed with screws as per details shown on drawings. Hold fasts/lugs shall be embedded in PCC (1:3:6) bed blocks of size 220mmx220mmx75mm in one brick thick walls and 100mmx220mmx75mm in half brick thick walls.

FLOORING

General adopted for laying floors and pavements.

Floors shall be laid to levels and as directed by the Engineer-in-Charge.

Floor topping of cast-in-situ cement concrete shall be finished even and smooth using extra cement as specified in CPWD specifications.

Pozzolana or pozzolana slag cement shall not be used for floor topping.

Floor finish over RCC slabs shall be laid all as specified.

Sub floor may not be laid in panels. The thickness of sub base concrete shall be as indicated in schedule.

CEMENT CONCRETE FLOORS: - PCC floors shall be provided as indicated in Schedule.

VITRIFIED TILES FLOORING

Where vitrified tiles specified on Schedules provide colored vitrified tiles of size as specified in the schedule and shall be laid and jointed pointed with white cement paste & pigment. Tiles shall confirm to IS - 15622-2006.

The tiles shall be first quality product procured from any of the manufacturers as listed in list of manufacturers

Laying jointing and finishing shall be all as per manufactures guidance/instructions.

The colour of tiles shall be as decided by Estate Officer and Engineer-in-Charge.

KOTA STONE SLAB FLOORING

Kota stone shall be hard, durable, regular in shape, of uniform colour and free from cracks, decay and weathering. It shall be set, jointed and pointed in neat cement slurry mixed with pigment to match with the colour of stone. The slabs used in one location shall be of uniform size and shall be laid over cement screed as indicated. Kota stone slabs shall be machine cut and true fine cut dressing on all sides up to full depth . All angles and edges shall be true, square, free from chipping and surface shall be true and plain. The joints of the tiles shall not be more than 1mm. Laying, polishing and finishing of kota stone shall be all as specified.

GLAZED CERAMIC TILE DADO

The ceramic dado shall be provided with ceramic tiles of size as specified in BOQ and shall be glazed quality colour and/or white as indicated in BOQ and conforming to relevant IS specifications.

The tiles shall be jointed and pointed with white or coloured cement to match with the colour of tiles. The tiles shall be laid over cement mortar screed as specified in BOQ.

GRANITE FLOORING /CILL

It shall be all as described on Schedule. Granite slab shall be machine cut, pre-polished, over cement screed 15mm thick in CM 1:6 over 25mm thick PCC 1:2:4 using 12.5mm aggregate over RCC slab or as per BOQ.

WHITE MARBLE TILE: 20mm thick makrana white marble tile shall be laid over cement screed CM 1:4, 15mm thick jointed with grey cement slurry mixed with pigment to match the shades of slab used as the boarder to kota slab flooring.

CERAMIC FLOOR/WALL TILES

Where Non-skid ceramic tiles specified on Schedules provide coloured non-skid ceramic tiles of size as specified in the schedule, as per Gde B II (a) shall be laid and jointed pointed with white cement paste & pigment. Tiles shall confirm to IS - 15622-2006.

The tiles shall be first quality product procured from any of the manufacturers as listed in list of manufacturers here-in-below.

Laying jointing and finishing shall be all as per manufactures guidance/instructions.

The colour of ceramic tiles shall be as decided by Estate Officer and Engineer-in-Charge.

PLASTERING AND POINTING GENERAL

Cement: Refer to specifications and list as mentioned above.

Fine aggregate for plastering and pointing work shall be river sand conform to IS 1542-1992 and as specified in Clause 14.5 to 14.5.2 of SSR Part I. Sand shall be obtained from sources as approved by Engineer-in-Charge.

Particular attention of the contractor is invited to take note of local practices and the local availability of materials like bricks form work etc and cater for any extra quantities of mortar required for rendering smooth for extra dubbing required for touching up properly and for smooth and even surfaces.

This shall be deemed to have been included in the lump sum.

Plaster and skirting/dado shall be returned in jambs, soffits of lintels and windows sills etc.

All plastered surface shall be trowel led to a smooth and even surfaces, without using extra cement.

Thickness of cement plaster mentioned hereinafter shall be finished thickness exclusive of dubbing. Dubbing may however be done in one operation with plaster.

Plaster on external surface shall be carried out upto 15cm below ground level or as per BOQ except where plinth protection/ramp etc are provided.

All corners, angles, junctions and riser shall be truly vertical or horizontal as the case may be and shall be carefully finished. Corners around jabs of openings and junction of walls shall be finished straight and square. 12mm wide groove at the junction of wall and RCC slabs to the entire thickness of wall plaster shall be provided. Also trowel groove shall be provided at junction of walls and RCC columns or any other dissimilar material e.g. wooden chowkhats etc.

Plastering shall be carried out all as specified in Schedule 'A'.

OIL EMULSION DISTEMPER

Distemper shall be applied as specified in BoQ. Preparation of surfaces and applications of distempering shall be all as per BOQ/CPWD specifications.

Preparation of surfaces and application of interior emulsion shall be done all as per manufacturer's instructions/ as specified in BOQ. The contractor shall give 05 years Guarantee for interior emulsion on stamp paper of value for Rs.100/-

CEMENT BASED PAINT

Cement based paint shall comply with IS 5410-1992, specification for cement paint colour as required. The material shall be in powder form, free from lumps that are not friable and when mixed with required volume of water shall be suitable for use on porous surfaces of masonry, concrete, bricks and rough plaster work. Cement base painting shall be provided where indicated in BOQ and all as specified.

WHITE/COLOUR WASHING

Lime shall be fresh burnt lime (Class 'C'), white in colour conforming to IS-712, 1984. The samples of lime, blue, sodium chloride and gum shall be approved the Engineer-in-Charge before incorporation in work. Workmanship shall be generally conforming to specification as described in Schedule.

SYNTHETIC ENAMEL PAINTING

The synthetic enamel paint shall be from any of the make/ brand listed in list of manufacturers.

Preparation of surfaces and application of synthetic enamel paint shall be done through the authorized applicator of approved manufacturer all as per manufacturer's instructions/ as specified in BOQ.

The colour scheme for building shall be got approved from Estate officer in consultation of Engineer-in Charge and the contractor shall progress the application of paint only on receipt of approval from Engineer- in-Charge.

GENERAL NOTES FOR APPLYING PUTTY, DISTEMPER, ANTIFUNGAL AND ENAMEL PAINTING

These works shall be executed using modern technics and tools to maintain the required quality work. Following smart painting tools shall be used in site.

- a. Hand held sander / long handle sander shall be used for plaster / puttywork.
- b. Multipurpose mixer shall be used for mixing putty to get a uniform mix.
- c. Auto roller and Airless spray shall be used for painting.
- d. Jet washer to be used for cleaning dirt and fungus etc from external walls.

WORKMANSHIP

All wood work required to be painted shall be smoothened sized and knotted and then applied with priming coat. Stopping and filling (filler coat) shall be done after priming coat and surface rubbed down to a level and smooth surface and thereafter under coat and finishing coat applied. Where painting to wood work is specified prepare surface and apply one priming coat of pink primer, one under coat and one finishing coat of synthetic enamel paint all as specified in Schedule/BOQ.

GALVANIZED SHEET

Galvanized steel sheet, plain or corrugated shall comply with the requirement of IS 277- 2003, Specification for galvanized steel sheets, plain or corrugated. The thickness sheet shall be 0.63mm and Grade of coating shall be 275 or as per BOQ

Plain sheets shall be reasonably flat and free from twist. Corrugated sheet shall be free from twist or buckle and shall have uniform corrugation, true in depth and pitch, and parallel to the sides of the sheets. The tolerance on weight of an individual sheet shall be $\pm 10\%$ and tolerance on bundle of sheets shall be $\pm 5\%$.

GALVALUME SHEETING:-

Galvalume sheet shall be colour coated corrugated / plain sheeting as per requirement and as directed. The feed material is manufactured out of steel with minimum 550 MPa yield strength coated with hot-dip metallic zinc aluminum alloy coating zinc alume AZ-150 or equivalent (as per AS 1397). AS150 Gms/sqm total on both sides of Zn (43.5%), Al (55%) & Si (1.5%) with Regular silicon modified(SMP)

polyester paint or equivalent as per AS/NZS-2728-(category 3-4) of approved colour. The colour shall have a total coating thickness of 35 microns of approved paint system or equivalent comprising of 20 microns (nom) exterior coat on top surface and 5 microns (nom) reverse coat of back surface over 5micron (nom) primer coat on both surfaces of approved colour shade.

The sheet shall have brand marking of the manufacturer on the back of the sheet at spacing not exc 1.5 m c/c confirming to genuineness of the material. The sheet shall be fastened with good quality fastener of suitable size as directed by Engineer -in-Charge/SI/Insp/Civil, galvanized water head, self-drilling, tapping screw as per AS 3566 class 4 (min) of approved make (Buildex, Corroshield or equivalent) and quality including EPDM/neoprene washer on each crest of sheets for connecting with purloins or as per design. All accessories shall be made from the same material which is used for main roofing/ wall cladding application.

INTERLOCKING PAVER BLOCK

Precast interlocking paver blocks shall be M 40/M-35 grade for 60/80mm thick and shall be laid over 30mm thick cushioning using 6mm and below aggregate or as per BOQ. The paver blocks shall be ISI marked having Glossy Finish. Paver blocks shall be sound and free from cracks or other defects. The tolerance in thickness shall be +3mm. Water absorption shall not be more than 6% by mass. Size, shape, pattern and colour shall be as approved Estate Officer in consultation with Engineer-in-Charge.

PRECAST PCC SOLID BLOCKS FOR MASONRY

SOLID PCC BLOCKS : PCC solid block masonry shall conform to the specifications as per IS 2185 -2005.

The blocks shall have a minimum average Compressive strength of 5 N/ Sq mm (Minimum strength of individual unit 4 N/ Sq mm) conforming to C-5 grade IS 2185 - 2005 when tested for 28 days cube test. The manufacture of Block, surface texture and finish, physical requirements of blocks, testing of PCC blocks, sampling etc shall be all as per IS 2185-2005 and proper record shall be maintained. The cost of blocks including transportation of block from work site to an approved laboratory for testing and cost of testing shall be borne by the contractor.

Notes:-

- i. Trial mix shall be carried out before casting the blocks to ensure that the required strength and block density is obtained as per IS.
- ii. Proper care shall be taken to protect the corners of PCC blocks. To achieve better consistency, contractor may use suitable plasticizers as approved by the Engineer-in-Charge without any price adjustment.

Masonry work shall be kept constantly moist for a minimum of 7 days. All concrete shall be mixed in mechanical mixer. The blocks shall be manufactured with vibratory moulding machines.. However, contractor may use machine moulds of other standard manufacturers if approved by Engineer-in-Charge. Appropriate consistency of concrete shall be used to enable de-moulding of the blocks immediately after casting. The blocks shall have sufficiently rough surface to afford a good key to the plaster and joints. The hardened blocks shall be cured in a water tank in curing yard and shall be kept continuously moist for 14 days. The curing water tank/yard must therefore be of adequate capacity/size. Curing shall be done as per IS -2185.

After curing, the blocks shall be dried for a period of 4 weeks before being used in

the work. The blocks shall be allowed to complete their initial shrinkage before they are laid in wall.

Chain Link Fencing :-Mild steel galvanized chain link fencing with mesh of size 50mm x50mm nominal dia of wire 3.10mm fixed to fencing posts sing suitable bolts and nuts.

HARD CORE

The materials for hard core shall be of broken granite stone to a gauge not exceeding 63mm and shall be free from dust and impurities.

Hard core shall be of stones/ boulders (Broken to gauge) not exceeding 63mm. Hard core shall be deposited spread and leveled in layers not exceeding 15cm thick and well watered, rammed to a true surface and compacted. The thickness of the hard core specified or as indicated in the drawings is the thickness after consolidation, where thickness had not indicated, it shall be 100 mm (consolidated thickness).

FORM WORK- As per CPWD Specifications.

GENERAL

- a. The work under these specifications consists of furnishing all labour , equipments and materials required for form work including all supporting structure for all works of cast in situ concrete as required by drawing and specification of contract.

(b) The contractor shall submit Form and Centering layout to SI/Insp Civil for checking and final approval by Engineer-in-charge and Estate officer. The complete final approval of the plan will be obtained by the contractor before such work is started on ground. The procedure of erection and removal of forms will be decided at this stage itself. These approvals shall not relive the contractor of any responsibility for correct and complete performance of all works included in the contract. The design and engineering of the formwork as well as its construction shall be the responsibility of the contractor.

ELECTRIFICATION

General-The scope of work consists of providing internal electric wiring to the buildings and connected other works as described in BOQ and as specified/Shown on drawings.

The general layout of wiring points and fittings are as directed by the Engineer in charge.

All electrical fittings and wiring must run clear of door, windows and openings No diagonal run shall be allowed. These must always be parallel or perpendicular to the ground.

The specification and general rules/conditions laid down in the CPWD Schedule(E&M) and CPWD Specifications will be generally applicable to the whole work unless otherwise specified hereinafter.

The work shall be carried out in strict compliance with the latest edition of Indian Electricity Act the Indian Electricity Rules and IEE Regulations and the latest edition of IS732. It shall be of high standard and approved construction used in a modern electrical work both as regards design and workmanship. Complete work shall be suitable in every respect of type of voltage specified and shall be to the satisfaction

of Engineer-in-Charge.

WORKMANSHIP

The work under internal electrification work shall be carried out only by licensed wireman under the supervision of shall produce (for inspection) license of electrician/wireman if ordered by the Engineer-in- Charge.

Passing of cables through walls floors etc shall be protected.

SAMPLES

Before starting the work, the contractor shall produce samples of all materials including accessories and got approved by the Engineer-in-Charge. Samples that are approved will be retained by Engineer-in-Charge until the work is completed and accepted. The contractor will not be allowed to commence the work before the samples are produced and approved. The contractor shall ensure that the materials used in the work are identical with approved samples and are uniform through out. All materials shall be accordance with latest edition of the IS/BS specification and shall be of the best indigenous make approved by the Engineer-in- charge.

MATERIALS : All materials shall be accordance with latest edition of the relevant IS/BS specification and shall be of indigenous make approved by Engineer-in-Charge.

CABLES: Cables shall be single core PVC insulated and PVC sheathed/unsheathed (all as described in BOQ). All cables shall be 1100 volts grade for point wiring and shall be of such size as to be capable to carrying the maximum current which will normally flow through them without the respective rating being exceeded as laid down in IEE Regulations.

Cables shall be delivered a site in makers wrappers etc, with the seal intact and shall not be installed unless approved by Engineer-in-charge. If cables of size as specified in BOQ as per relevant IS are not available, cables of equivalent size with identical current carrying capacity and with multi-stands shall be got approved from accepting office before incorporation works without extra cost to Govt.

MS PRESSED STEEL TERMINAL BOXES

Mild steel pressed terminal boxes shall be made out of 2 thick MS sheet of suitable size. The boxes shall be embedded in the walls with cement mortar (1:2) clear depth of the box shall be not less than 60mm and this shall be increased suitability to accommodate mounting of fan regulators. The box shall be painted with one coat of red oxide primer.

LAMINATED SHEET

Laminated sheet shall be 3mm thick fixed in MS pressed steel terminal boxes by cadmium plated iron screws

CIRCUITS

Separate circuits shall be provided for lighting and power wiring. Lighting sub circuits shall not be loaded with more than 8 light points.

CONDUIT AND CONDUIT ACCESSORIES: All conduits, conduit fittings and accessories shall be rigid PVC conduit and fittings conforming to IS-9537 Part III of 1983 of (Medium grade).

CEILING ROSES: Ceiling roses shall be ISI marked.

SOCKET OUTLETS: These shall be ISI marked.

MINIATURE CIRCUIT BREAKERS AND DISTRIBUTION BOARDS

MCB shall be of approved make and shall be obtained from any one of the manufacturers listed above. The unused portion of DBs are to be blocked by the blank piece.

FAN REGULATOR: Fixing of fan regulator and hanging ceiling. All ceiling fans and regulators shall be earthed effectively by means of 2mm bare GI iron conductors. Cost of this earthing to fans and regulators shall be deemed to be included in the rate for point wiring for fans.

EARTHING : Earthing shall be carried out as specified in BOQ. Earthing shall be with earth plate electrode as mentioned in BOQ buried directly in ground (earth pit) not less than 2.25m deep below ground level connected to galvanized earth top edge of the plate not less than 1.5m below ground level connected to earth strip as mentioned in BOQ by means of bolt nut and washers of galvanized iron or steel, and protected by GI pipe light grade of suitable size. Excavation and earth work shall be in soft/loose soil. All surplus soil to be removed to a distance not exceeding 50m. Cement concrete for PCC chamber , cover slab, reinforcement etc shall be as per BOQ. The unit rate of relevant item of BOQ including the cost of earth work, PCC Chamber, RCC cover, testing etc complete.

LED LIGHT FITTING: These shall be all as specified in BOQ and shall be obtained from any of the manufacturer listed here in after and shall be fixed to walls/roofs etc with proper size of clamps/screws and connecting cables etc complete.

PAINTING: Unless otherwise specified all exposed surface of steel works like terminal boxes LT panel board MS clamps etc shall be painted with 2 coats of synthetic enamel paint over a coat of red-oxide primer. Metallic suspenders of tube light fittings shall be black painted.

SYSTEM OF WIRING: Wiring shall be carried out with PVC insulated cable and shall run as far as possible on walls, ceilings so as to be easily accessible and capable of being inspected. Power wiring shall be kept apart at minimum distance of 2 run unless they are enclosed in earthed metal conduit suitably marked to indicate the risk of dangerous shock due to voltage in the conductor.

CONCEALED WIRING: Provide concealed wiring all as described in BOQ. PVC conduit shall be rigid PVC conforming to relevant IS. The make of PVC conduit as mentioned above. PVC conduit shall be adequate size to draw required for cables.

TESTING

On completion of the work, the entire electrical installation including energy meter shall be tested by the contractor for the necessary following tests in the presence of and to the satisfaction of Engineer-in-Charge :-

- a. Continuity
- b. Insulation resistance
- c. Any other test prescribed by the Engineer-in-Charge

All testing equipment/apparatus, material, labour etc required for above tests shall be provided by the contractor at his own expenses through his sources, works for

which test results do not conform to standard will be redone by the contractor at his own expenses.

RECORD DRAWINGS: On completion of work, wiring diagram showing the internal electrification

(including high frequency supply) and layout of the buildings shall be prepared by the contractor at his own expenses through his sources and submitted to Engineer-in-Charge in triplicate.

SUB MAIN WIRING

CABLES:- Cables shall be single core PVC insulated and PVC sheathed/unsheathed(all as described in BOQ' with multistranded copper conductor conforming to specifications. All cables shall be 1100 volts grade for point wiring and shall be of such size as to be capable to carrying the maximum current which will normally flow through them without the respective rating being exceeded as laid down in IEE Regulations. Cables shall be delivered at site in makers wrappers etc, with the seal intact and shall not be installed unless approved by the Engineer-in-charge.

CONDUIT WIRING: Provide PVC conduit wiring all as described in BOQ. PVC conduit shall be rigid medium grade PVC conforming to relevant IS. The make of PVC conduit shall be as specified in here-in- after . PVC conduit shall be of adequate size to draw required No of cables.

System of wiring: Wiring shall be carried out with PVC insulated cable and shall run as far as possible on walls, ceiling so as to be easily accessible and capable of being inspected. Power wiring shall be kept apart at minimum distance of 2mm unless they are enclosed in earthed metal conduit suitably marked to indicate the risk of dangerous shock due to voltage in conductor.

DISMANTLING/ DEMOLITION/ TAKING DOWN: The work of dismantling/ demolition/ taking down shall be done carefully and in a workman like manner. Any damage done by contractor or his workmen to existing sanitary fittings/ water supply fittings/ electrical fittings etc in the building while working shall be made good by him at his own expense. All the materials retrieved from demolition/ dismantling/ taking down shall become the Government property except those listed in Credit Schedule. The rates inserted by the CPWD or quoted by the contractor (whichever is more) shall be deemed to include removal or disposal of all waste materials from site of work and site shall be left clean and tidy to the entire satisfaction of Engineer-in-Charge.

SITE CLEARANCE

The contractor shall from time to time, clear away all debris and excess materials accumulated at the site. After the fixtures, etc have been fixed, contractor shall clean-up the same and remove all paints, strains and other foreign matter or discoloration leaving the same in a ready to use condition. On completion of all works, contractor shall demolish all stores, remove all surplus materials and leave the site in a broom clean condition.

SETUP OF FIELD SAMPLE TEST LABORATORY:- Contractor will setup a laboratory at site for testing of sample i.e. cube testing, Sand test, gravel testing, cement testing, sieve analysis, CBR test, Compressive strength machine, Los angles abrasion, Slump test, Silt test of sand etc.

Sd/-12-07-2026

**LT. COLONEL ANAND KUMAR
COMDT**

Contract Cell, NEZ HQr
[For and on behalf of the President of
India]

Annexure-I

SCHEDULE OF QUANTITY

Tender Enquiry No. :- 03-NEZ-C/Cell-GC GTY/MW/2026-27		Dated- 12-07-2026	
Name of Work :- Repairing of Badminton Court at GC CRPF Guwahati, Assam.			
Location of Work : Group Centre CRPF Guwahati, Assam-781023			
SL. No.	Items / Description of Work	Qty.	Unit
Part-1 [Civil Work]			
1	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:		
1.1	1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.51	Cum
2	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	79.92	Sqm
3	Reinforced cement concrete work in beams, suspended floors, roofshaving slope up to 15° landings, balconies, shelves, chajjas, lintels, bands,plain window sills, staircases and spiral stair cases above plinth level upto floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.40	Cum
4	Centering and shuttering including strutting, propping etc. and removalof form for		
4.1	Suspended floors, roofs, landings, balconies and access platform with water proof ply 12 mm thick	4.00	Sqm
5	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete above plinth level.		
5.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	34.00	Kg

6	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	9.30	Sqm
7	Providing and fixing chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete :		
7.1	20 mm dia metre	3.20	Metre
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :		
8.1	150x10 mm	4.00	Each
9	Providing and fixing ISI marked IS:1341 M.S. pressed butt hinges bright finished with necessary screws etc. complete :		
9.1	100x58x1.90 mm	6.00	Each
10	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :		
10.1	100 mm	6.00	Each
11	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.		
11.1	Single rubber stopper	4.00	Nos
12	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete		
12.1	250x16 mm	4.00	Each
13	Providing & fixing fly proof wire gauze to windows, clerestory windows & doors with M.S. Flat 15x3 mm and nuts & bolts complete.		
13.1	Stainless steel (grade 304) wire gauze of 0.5 mm dia wire and 1.4 mm aperture on both sides	2.16	Sqm
14	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	9.00	Sqm
15	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.		
15.1	110 mm diameter	73.50	Metre
16	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.		
16.1	110x110x110 mm, Single tee with door	7.00	Each
16.2	110x110x110 mm, Single tee without door	7.00	Each
16.3	110 mm bend, Bend 87.5°	14.00	Each
17	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and		

17.1	making good the wall etc. complete.	14.00	Each
18	Finishing walls with Acrylic Smooth exterior paint of required shade :		
18.1	New Work (Two or more coat applied @ 1.67 ltr/ 10 sqmover and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	904.62	Sqm
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :		
19.1	Two or more coats on new work	18.14	Sqm
20	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1773.66	Sqm
21	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	1773.66	Sqm
22	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.		
22.1	New work (two or more coat)	869.04	Sqm
23	15 mm cement plaster on the rough side of single or half brick wall of mix :		
23.1	1:4 (1 cement: 4 fine sand)	370.50	Sqm
24	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge	9.00	Sqm
25	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in Charge	2.00	Each
26	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	2.00	Each
27	Cleaning of choked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. Dechocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm	18.00	Metre
28	Disconnecting damaged overhead/terrace PVC water storage tank of any size from water supply line and removing from the terrace including shifting at ground level as per direction of Engineer-in-charge.	2.00	Each
29	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	4.00	Each
30	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.		
30.1	With cement mortar 1:4 (1 cement : 4 fine sand)	60.79	Sqm
31	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :		
31.1	Of area 3 sq. metres and below	4.00	Each
32	Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead :		
32.1	100 mm dia pipe	36.00	Metre
33	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	370.50	Sqm

34	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:		
34.1	White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	2.00	Each
35	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.		
35.1	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	2.00	Each
36	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.		
36.1	Semi rigid pipe 40 mm dia	2.00	Each
37	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C.flushing cistern, including flush pipe, with manually controlled device(handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :		
37.1	W.C. pan with ISI marked white solid plastic seat and lid	2.00	Each
38	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleat with C.P. brass screw and washers complete.	2.00	Each
39	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls		
39.1	20 mm nominal dia Pipes	20.00	Metre
40	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.External work		
40.1	25 mm nominal dia Pipes	20.00	Metre
40.2	40 mm nominal dia Pipes	10.00	Metre
41	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.		
41.1	15 mm nominal bore	2.00	Each
42	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :		
42.1	15 mm nominal bore	4.00	Each
43	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :		
43.1	25 mm nominal bore	2.00	Each
44	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes and the base support for tank.	1000.00	Litre
45	Providing and fixing PTMT grating of approved quality and colour.		
45.1	Circular type 100 mm nominal dia	4.00	Each
46	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :		
46.1	25 mm nominal bore	2.00	Each
47	Providing and fixing PTMT soap Dish Holder having length of 138mm,		

	breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	2.00	Each
48	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931		
48.1	15mm nominal bore	8.00	Each
49	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour.		
49.1	20 mm nominal bore, weighing not less than 40 gms	4.00	Each
50	Providing and fixing uplasticised PVC connection pipe with brass unions :		
50.1	30 cm length 20 mm nominal bore	2.00	Each
51	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm ² , modulus of elasticity 850 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately)		
51.1	30 mm thick	6.97	Sqm
52	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Clerestory windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm ² , modulus of elasticity 900 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately).		
52.1	Frame size 45 x 70 mm	19.80	Metre
53	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately)		
53.1	For fixed portion		
53.2	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	126.00	Kg
53.3	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/neoprene gasket required (Fittings		
53.4	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	217.80	Kg
55	Providing and fixing glazing in aluminium door, window, ventilator shutters		

	and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.		
55.1	With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	0.72	Sqm
56	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	1.80	kg
57	Surface Preparation : cleaning the entire surface with grinding and removing the loose mortar, dust particles & making the surface sound enough, addressing the cracks by making V groove & if any surface imperfections are treated with neat Repair polymer or equivalent, mixed with neat cement in 1:1 proportion. Treating all construction jointa as per direction of Engineer-in-charge.Primer: Suppling and applying one coat of primer with water-based epoxy primer, Epoxy Primer/Solvent Based HFP 130/120/Equivalent @ 200 Gms/Sqm.Waterproofing : Supplying and applying single component PU Magnam US or equivalent,Zero VOC, elastomeric pure polyurethane membrane free from bitumen and tar, PU Magnum US with minium ekongation of 500% solid 85 % , Tensile strength of >3 Mpa,crack bridging capacity of 3mm and shore hardness of >50. The system consists of applying the PU Magnum US waterproofing @1.8/sqm. in two coats as per direction of Enigneer-in-charge. Actual area treated will be the mode of measurement. Geotextile : Providing and laying 200 gsm geotextile over the waterproofing PU with and overlap of 50 mm.	510.50	Sqm
58	Screed Concrete: Application of screed by making slope with 50 mm avg. thick M20 grade screed admixed with Vitalia Neo or equivalent @the rate of 200 ml per bag of cement. The screed to be laid in slope 1:100 or as per client recommendations.	510.50	Sqm
Part-2 [Electric Work]			
59	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.		
59.1	Group-A	36.00	Point
60	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		
60.1	5/6 A switch	22.00	Each
60.2	3 pin 5/6 A socket outlet	6.00	Each
61	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.		
61.1	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	160.00	Metre
61.2	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	56.00	Metre
62	Supplying and fixing Brass batten/ angle holder including connection etc. as required	8.00	Each
63	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	4.00	Each
64	Supplying and fixing following rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.		
64.1	63A	2.00	Each
65	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve,		

	miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning		
65.1	Single pole and neutral	4.00	Each
66	Providing and fixing of 300 mm (40 watt) metal body sweep exhaust fan complete with all accessories, fixing with suitable frame, connecting with existing electrical point using required length of PVC insulated copper wire, testing and commissioning, complete as required.	6.00	Nos.
67	Providing and fixing of LED Tube/batten lights 20 watt of approved make with necessary all accessories and complete works	6.00	Nos.
68	Providing and fixing of LED bulb 12 watt of approved make with necessary all accessories and complete works	6.00	Nos.

Note :-

- i. The lowest bidder will be decided on overall rate of entire work instead of item (category) wise. Rates quoted by the bidder must be inclusive of applicable G.S.T (Goods and Services Tax) and all other charges if any but exclusive of EPF & ESI Contributions on the part of Employer as applicable with F.O.R (Site of work) at **O/O The DIG Group Centre CRPF Guwahati, Assam-781023.**
- ii) The E.P.F & E.S.I contributions on the part of employer in respect of the contract shall be paid by the contractor to concerned department well in time. These contributions on the part of the employer paid by the contractor shall reimbursable by this department on actual basis and on production of receipt of the concerned department.

[_____]

Signature of Bidder
(with seal)

Sd/-12-07-2026
LT. COLONEL ANAND KUMAR
COMDT
Contract Cell, NEZ HQR
[For and on behalf of the President of India]